

Contents

- 10A. Construction Noise and Vibration Data
- 10B. Initial Construction Traffic Noise Assessment

Grimsby to Walpole Document control

Document Properties	
Organisation	Arup AECOM
Approved by	National Grid
Title	Preliminary Environmental Information Report Volume 3 Part B Section Specific Assessments Section 4 New Lincolnshire Connection Substation B to Refined Weston Marsh Substation Siting Zone Chapter 10 Noise and Vibration Appendices
Document Register ID	GWNC-ARUP(AEC)-ENV-REP-0002
Data Classification	Public

Date	Version	Status	Description / Changes
June 2025	1.0	Final	First Issue

10A. Construction Noise and Vibration Data

Contents

10A.1 10A.2	Introduction Construction	on Noise on Plant Data	1 1 1 1 4
		on Vibration Introduction of Construction Vibration	4
		Construction activity plant and noise data Indicative construction vibration threshold distances	2 5
	References		6

10A. Construction Noise and Vibration Data

10A.1 Introduction

- 10A.1.1 This appendix presents information and data used within the assessment of Noise and Vibration effects from construction activities at Noise and Vibration sensitive receptors (NSR) in the New Lincolnshire Connection Substation (LCS) B to Refined Weston Marsh Substation Siting Zone Section (Section 4) as part of the Grimsby to Walpole Project (the Project). This appendix includes:
 - construction noise data: and
 - ii. construction vibration data.

10A.2 Construction Noise

10A.2.1 The construction noise assessment has been undertaken in accordance with the methods and empirical data outlined in British Standard (BS) 5228-1:2009+A1:2014 Code of practice for Noise and Vibration control on construction and open sites – Part 1: Noise (BS 5228-1) (Ref 1).

Construction Plant Data

Indicative construction plant and data associated with each proposed construction activity is **Table 1A.1**. The table provides the average expected sound pressure level as A-weighted decibels (dBA) for each activity at a standard distance of 10 m. The construction noise assessment takes these values and corrects for the distance between the construction activity and each NSR within the Study Area in accordance with the methodology described in BS 5228-1. For the purposes of the assessment, attenuation from mitigation measures, such as screening, is not included. This is so that noise 'hot spots' can be identified, and specific mitigation measures can be identified where they are required to avoid significant adverse effects.

Table 1A.1 Construction activity plant and noise data

Activity	Plant Item	Number of Plant Items	BS 5228-1 Ref	Per cent on time	A-weighted Sound Pressure Level at 10 m, dBA	Average Activity Sound Pressure Level at 10 m, dBA
General Works						
Site preparation	Tracked excavator	2	C2.7	70	70	79
	Dozer	3	C2.1	70	75	
Top soil strip	Tracked excavator	2	C2.7	70	70	79
	Dozer	3	C2.1	70	75	
Temporary access route	Wheeled backhoe loader	1	C2.8	70	68	79
	Dumper	2	C4.4	70	76	
	Vibratory roller	1	C2.40	70	73	
Temporary Cons	struction Compo	unds				
Site preparation	Tracked excavator	2	C2.7	70	70	79
	Dozer	3	C2.1	70	75	
Road	Dumper	3	C4.4	70	76	
construction	Road Roller	1	C5.19	70	80	82
Compound	Telehandler	2	C4.55	50	70	
buildings	Generator	2	C3.33	100	57	70

Activity	Plant Item	Number of Plant Items	BS 5228-1 Ref	Per cent on time	A-weighted Sound Pressure Level at 10 m, dBA	Average Activity Sound Pressure Level at 10 m, dBA
Compound	Lorry	1	C2.34	25	80	76
operation	Telehandler	2	C4.55	50	70	
	Generator	2	C3.33	100	57	
Overhead Line C	Construction					
Pylon construction	Tracked excavator	1	C2.7	70	70	83
	Steel tube piling rig	1	C3.8	25	88	
	Concrete pump	1	C3.26	50	75	
Pylon Assembly	Telehandler	1	C4.55	50	70	67
Pylon installation	Crane lifting pylon	1	C4.46	10	67	57
Cable tensioning	Winder	1	Suppliers' data	60	77	78
	Rear Winder	1	Suppliers' data	60	77	

10A.3 Construction Vibration

Construction Vibration Introduction

- 10A.3.1 The construction vibration assessment has been undertaken with reference to the methods and empirical data outlined in BS 5228-2:2009+A1:2014 Code of practice for Noise and Vibration control on construction and open sites Part 2: Vibration (BS 5228-2) (Ref 2).
- 10A.3.2 The main significant sources of vibration during construction activities are expected to be ground compaction, and percussive or vibratory piling. These processes may be required during the following activities:
 - i. Ground compaction with vibratory roller:
 - setup of site compounds:
 - site preparation;
 - temporary access route construction; and
 - cable laying.
 - ii. Piling:
 - pylon foundations.

Prediction of Construction Vibration

10A.3.3 Peak particle velocity (PPV) vibration levels in millimetres per second (mm/s) generated by ground compaction and piling activities can be predicted using the guidance and empirical formulae in Table E1 of BS 5228-2. The formulae are shown below.

Vibratory roller calculation formula

$$v_{res} = k_s \sqrt{n_d} \left[\frac{A}{x + L_d} \right]^{1.5}$$
 (Equation 1)

Where:

- i. $V_{res} = Resultant PPV$, in millimetres per second (mm/s).
- ii. k_s = Scaling factor (and probability of predicted value being exceeded).
- iii. $n_d = Number of vibrating drums$.
- iv. A = Maximum amplitude of drum vibration, in millimetres (mm).
- v. x = Distance measured along the ground surface, in metres (m).
- vi. L_d = vibrating roller drum width, in metres (m).

Percussive piling calculation formula

$$v_{res} \le k_p \left[\frac{\sqrt{W}}{r^{1.3}} \right]$$
 (Equation 2)

Where:

- i. V_{res} = Resultant PPV, in millimetres per second (mm/s).
- ii. $K_p = Scaling factor (depending on soil conditions).$
- iii. W = Nominal hammer energy, in joules (J).
- iv. r = Slope distance from the pile toe, in metres (m).

Assumptions

- 10A.3.4 The following conservative assumptions have been made to predict vibration levels to assess a reasonable worst-case:
 - Vibratory Roller assumptions:
 - scaling factor of 75, representative of average conditions; and
 - vibratory roller data based on worst case Bomag BW 213, 1 drum of 2.13 m width and maximum amplitude of 1.1 mm.
 - ii. Percussive piling assumptions:
 - typical value of nominal hammer energy of 25 kJ; and
 - scaling factor of 1.5 representative of typical soil conditions.

Vibration prediction results

10A.3.5 Equations 1 and 2 have been used to predict the minimum distances within which the vibration threshold values human comfort impacts from vibration in terms of the significant observed adverse effect level (SOAEL) and potential cosmetic building damage threshold may be exceeded (1.0 mm/s, and 12.5 mm/s PPV respectively). The calculated distances in **Table 1A.2** are used in the preliminary assessment to identify areas where NSR, and buildings and structures are potentially affected by construction vibration.

Table 1A.2 Indicative construction vibration threshold distances

Activity	Distance Within Which SOAEL May Be Exceeded (m)	Distance Within Which Cosmetic Building Damage May Occur (m)
Ground compaction	18	<2
Percussive piling	70	<10

References

- Ref 1 BS 5228-1:2009+A1:2014 Code of practice for noise and vibration control on construction and open sites Part 1: Noise, British Standard Institution, 2014.
- Ref 2 BS 5228-2:2009+A1:2014 Code of practice for noise and vibration control on construction and open sites Part 2: Vibration, British Standard Institution, 2014

10B. Initial Construction Traffic Noise Assessment

Contents

10B.	Initial Con	nstruction Traffic Noise Assessment						
10B.1	Introduction		1					
10B.2	1 1 1 1							
10B.3	Assessmen	t	2					
	Table 10B.1	Construction traffic noise assessment	4					
	References		9					

10B. Initial Construction Traffic Noise Assessment

10B.1 Introduction

10B.1.1 This appendix presents the initial assessment of construction traffic noise affecting Noise and Vibration sensitive receptors (NSR) in the New Lincolnshire Connection Substation (LCS) B to Refined Weston Marsh Substation Siting Zone Section (Section 4) as part of the Grimsby to Walpole Project (the Project).

10B.2 Assessment Methodology

10B.2.1 The assessment of construction traffic noise has been conducted following the guidance detailed in Design Manual for Roads and Bridges LA 111 (DMRB LA 111) (Ref 1). This provides guidance for the assessment and Noise and Vibration impacts from road projects; however, the guidance is widely used in the assessment of construction Noise and Vibration impacts from other types of project, particularly with regards to construction traffic noise in lieu of other guidance.

Data Sources

10B.2.2 The assessment is based on traffic data and assumptions that has been produced by National Grid Electricity Transmission plc (National Grid) to support the transport assessment, including the proposed numbers of heavy goods vehicles (HGV).

Study Area

10B.2.3 Noise from construction traffic on the existing local road network has been assessed based on the proposed construction traffic routes. The Study Area is defined following the guidance detailed in DMRB LA 111 which states that the construction traffic Study Areas shall be defined to include a 50 m width from the kerb line of public roads with the potential for an increase in basic noise level (BNL) of 1dB(A) or more because of the additional construction traffic to existing traffic levels.

Assessment Criteria

Noise from construction traffic on the public highway has been calculated in accordance with the Calculation of Road Traffic Noise (CRTN) (Ref 2) and assessed against the criteria detailed in DMRB LA 111. The BNL from public roads used as construction traffic routes has been calculated in accordance with CRTN for the Dominimum and Do-something scenarios in the construction period. The calculated BNL values were compared to determine the magnitude of the impact.

- The BNL is a standardised metric for determining the noise level from a road and is defined as the noise level exceeded for 10 per cent of the time at a reference of 10 m away from the nearside carriageway edge obtained from traffic flow, speed, and is calculated in line with the methodology described in CRTN.
- 10B.2.6 Calculations are based on the Annual Average Weekday Traffic (AAWT) over the 18-hour period between 06:00 and 00:00 (AAWT,18 h). The standard CRTN BNL calculation is applicable where the AAWT,18 h traffic flows are greater than 4000 vehicles per 18-hour day. Where flows are between 1000 and 4000 vehicles per day, a 'low flow' correction can be applied which is a function of the distance from the carriageway. For the purposes of the initial assessment, a typical worst-case distance of 10 m has been assumed (the correction reduces with increased distance, with no correction applied beyond 30 m).
- 10B.2.7 Where there are potential changes in the BNL on roads greater than or equal to 1dB(A) a subsequent assessment of the impacts has been conducted on NSR within 50 m of routes where there are potential significant effects. NSR include dwellings, healthcare facilities, education facilities or other buildings where noise can cause disturbance to people using the buildings.
- 10B.2.8 Construction traffic noise effects are significant where there are medium or large magnitude impacts for a duration of ten or more days in any 15 consecutive days or for a total number of days exceeding 40 in any six consecutive months. A detailed program of works is not currently available. However, for the purpose of this initial assessment it is assumed that the above temporal thresholds may be exceeded, as a worst-case.
- 10B.2.9 There are also potential significant effects were there is a small magnitude impact at NSR located within Noise Important Areas (NIA), which are more sensitive to increases in noise. NIAs are determined via strategic noise maps and highlight the residential areas experiencing the highest 1 per cent of noise levels from road and rail sources in England.

10B.3 Assessment

- 10B.3.1 The results of the construction traffic noise assessment are provided in **Table 10B.1**. It is assumed that there is no change in average speed between the do-minimum and do something scenarios. The results are colour coded as follows:
 - i. Green Negligible magnitude impact (neutral)
 - ii. Yellow Small magnitude impact (no NIA) (negative)
 - iii. Orange medium magnitude impact, or small magnitude with NIA (negative)
 - iv. Red Large magnitude impact (negative)
- 10B.3.2 Construction traffic noise impacts have been assessed on 41 construction traffic road links in Section 4 where data is available. The assessment indicates that construction traffic would lead to the following impacts:
 - i. no change in noise level on 14 road links; and
 - ii. a negligible increase in noise level on 25 road links;
 - iii. a small increase in noise level on two road links (none of which include NIAs).

10B.3.3 No medium or large magnitude construction traffic noise impacts are expected in Section 4. Additionally, there are no small magnitude impacts in locations which include NIAs (where a small magnitude impact may be considered significant). Therefore, there are no likely significant effects from construction traffic noise in Section 4.

Table 10B.1 Construction traffic noise assessment

Access Route Name/ID	Road Name	Baseline Data		Baseline I Plus Cons Traffic		BNL, dB L _{A10,18h}		Change, dB	Outcome magnitude and effect.
		Total Daily Vehicles	Per cent HGV	Total Daily Vehicles	Per cent HGV	Baseline	Baseline Plus Construction Traffic		
CR8	A16	5519	9.1	6032	15.7	69.7	71	1.3	Small magnitude. Not Significant
CR25	A158	7648	5.1	8008	10.5	70.4	71.5	1.1	Small magnitude. Not Significant
LK44	Fodderdyke Bank	1562	11.3	1623	14.7	63.2	64	0.8	Negligible magnitude. Not Significant
CR9-3	A16	6008	7.6	6250	9.9	68.2	68.9	0.7	Negligible magnitude. Not Significant
LK34	B1195	1255	1.3	1282	3.0	59.7	60.3	0.6	Negligible magnitude. Not Significant
CR9-1	A16	9309	8.2	9627	9.6	71.8	72.2	0.4	Negligible magnitude. Not Significant
LK49	B1183 Carrington Road	1351	14.8	1416	15.3	62.7	63.1	0.4	Negligible magnitude. Not Significant

Access Route Name/ID	Road Name	Baseline Data		Baseline I Plus Cons Traffic		BNL, dB L	BNL, dB La10,18h		Outcome magnitude and effect.
		Total Daily Vehicles	Per cent HGV	Total Daily Vehicles	Per cent HGV	Baseline	Baseline Plus Construction Traffic		
LK51	B1184 Canister Lane	1485	18.9	1531	19.5	63.9	64.2	0.3	Negligible magnitude. Not Significant
CR9-2	A16	12148	5.6	12458	6.8	72.5	72.8	0.3	Negligible magnitude. Not Significant
CR11-2	A16	17956	10.6	18308	11.9	75	75.3	0.3	Negligible magnitude. Not Significant
CR14-1	A17	16484	20.6	16853	22.4	76	76.3	0.3	Negligible magnitude. Not Significant
CR14-3	A17	13609	18.0	13949	20.1	74.9	75.2	0.3	Negligible magnitude. Not Significant
CR9-4	A16	8943	13.5	9096	14.0	71	71.2	0.2	Negligible magnitude. Not Significant
CR11-1	A16	20293	17.0	20634	18.2	76.5	76.7	0.2	Negligible magnitude. Not Significant
CR14-2	A17	21293	20.3	21656	21.7	77.1	77.3	0.2	Negligible magnitude. Not Significant

Access Route Name/ID	Road Name	Baseline Data			Baseline Data Plus Construction Traffic		BNL, dB L _{A10,18h}		Outcome magnitude and effect.
		Total Daily Vehicles	Per cent HGV	Total Daily Vehicles	Per cent HGV	Baseline	Baseline Plus Construction Traffic		
CR16	A1121	7605	9.5	7658	10.1	68	68.2	0.2	Negligible magnitude. Not Significant
LK11	A158	11378	3.4	11502	4.4	71.8	72	0.2	Negligible magnitude. Not Significant
LK27	B1449 Thurlby Road	2654	12.0	2715	12.6	66.7	66.9	0.2	Negligible magnitude. Not Significant
LK35	Ingoldmells Road	1244	9.9	1256	10.7	61.3	61.5	0.2	Negligible magnitude. Not Significant
LK57	Punchbowl Lane	2229	9.1	2245	9.7	65.2	65.4	0.2	Negligible magnitude. Not Significant
LK59	B1192 Frampton Fen Ln Hollmes Road	1400	12.6	1411	13.2	62.6	62.8	0.2	Negligible magnitude. Not Significant
CR22-1	A17	19349	13.5	19500	13.8	75.8	75.9	0.1	Negligible magnitude. Not Significant

Access Route Name/ID	Road Name	Baseline Data		Baseline I Plus Cons Traffic		BNL, dB LA	BNL, dB L _{A10,18h}		Outcome magnitude and effect.
		Total Per Total Per Baseline Baseline Plus Daily cent Daily cent Construction Vehicles HGV Vehicles HGV Traffic							
CR26	A52	7359	8.5	7414	8.7	70.8	70.9	0.1	Negligible magnitude. Not Significant
LK50	B1184 Westville Road	1653	13.5	1660	13.8	61	61.1	0.1	Negligible magnitude. Not Significant
LK64	B1397	4533	17.6	4545	17.8	70	70.1	0.1	Negligible magnitude. Not Significant
LK81-1	A158	22224	2.4	22335	2.8	74.5	74.6	0.1	Negligible magnitude. Not Significant
W39	A155	3181	6.3	3249	6.1	66.7	66.8	0.1	Negligible magnitude. Not Significant
CR9-5	A16	24205	7.1	24283	7.1	72.5	72.5	0.0	No change. Not Significant
CR9-6	A16	23141	4.8	23227	4.8	72.6	72.6	0.0	No change. Not Significant
CR9-7	A16	45163	3.5	45243	3.5	75.1	75.1	0.0	No change. Not Significant
CR10	A16	21912	6.5	22017	6.4	75.2	75.2	0.0	No change. Not Significant

Access Route Name/ID	Road Name	Road Name Baseline Data		Baseline I Plus Cons Traffic		BNL, dB LA	BNL, dB L _{A10,18h}		Outcome magnitude and effect.
		Total Daily Vehicles	Per cent HGV	Total Daily Vehicles	Per cent HGV	Baseline	Baseline Plus Construction Traffic		
CR17-1	A52	18362	3.7	18362	3.7	70.3	70.3	0.0	No change. Not Significant
CR17-2	A52	14451	4.5	14456	4.5	73	73	0.0	No change. Not Significant
LK28	A1028	5953	4.6	5963	4.6	69.2	69.2	0.0	No change. Not Significant
LK39	Lymn Bank	1225	16.8	1234	17.0	62.2	62.2	0.0	No change. Not Significant
LK60	B1391	4977	10.4	4997	10.8	69.5	69.5	0.0	No change. Not Significant
LK81-2	A158	14809	10.3	14833	10.4	71.1	71.1	0.0	No change. Not Significant
W46	A52	6725	9.0	6751	9.0	70.5	70.5	0.0	No change. Not Significant
W47	Quadring Road	5341	5.4	5368	5.3	67.3	67.3	0.0	No change. Not Significant
W81	A52 Wainfleet Road	8521	6.3	8526	6.3	69.5	69.5	0.0	No change. Not Significant
W82	B1183	7615	2.9	7631	2.9	68.2	68.2	0.0	No change. Not Significant

References

- Ref 1 Highways England et al. (2020). Design Manual for Roads and Bridges LA 111 Noise and vibration.
- Ref 2 Department of Transport. (1988). Calculation of Road Traffic Noise.

National Grid plc National Grid House, Warwick Technology Park, Gallows Hill, Warwick. CV34 6DA United Kingdom

Registered in England and Wales No. 4031152 nationalgrid.com