

Innovation Funding Incentive Annual Report 2008/09 Section 3



Gas Transmission R&D Programme Detailed Reports





National Grid Gas Transmission R&D Programme Detailed Report

During the financial year 2007/2008 National Grid Gas Transmission utilised the Innovation Funding Incentive across a number of projects. In accordance with Innovation Good Practice Guide for Energy Networks (ENA Engineering Recommendation G85 Issue2), projects with an annual spend of under £80,000 have been combined with other projects to form programme areas. These programme areas can be seen below and the progress reports can be seen over the next few pages.

National Grid Gas Transmission R&D Programmes

- 1 External Contamination Detection and Measurement at Entry Points
- 2 Research into Connections to X80 Grade Pipeline Material
- 3 Hydrocarbons [Effects of Higher Hydrocarbon Content on the Safety of Natural Gas Transmission]
- 4 Detection & Management of Corrosion
- 5 Pipeline Fatigue Factors and Pipeline Repair Techniques
- 6 Research into the Potential for Vegetation to Damage Transmission Pipelines
- 7 Software Tools for Hazard and Risk Assessment of Major Hazard Gas Pipelines
- 8 Pipeline Inspection Techniques
- 9 Use of Alternative Techniques for Reducing Third Party Interference
- 10 Investigating Ground Conditions for Asset Construction and Performance
- 11 Efficient Asset Management
- 12 Compressor Asset Research
- 13 Research into Valve Life , Maintenance and Replacement
- 14 AGI Meter Modification to Increase Efficiency
- 15 Research into the Affect of Design and External Factors on Metering Assets
- 16 Ensuring Safety on Gas Transmission Sites
- 17 Reducing Environmental Impact by Understanding/Reducing Methane Emissions
- 18 Reducing National Grid's Carbon Footprint
- 19 Flooding Risk Analysis
- 20 Asset Management and Performance of Enegy Systems (Amperes)
- 21 PRCI
- 22 Carbon Capture and Storage (Strategic Overview)
- 23 Reuse of Transmission Assets for the Transportation of CO2





1) External Contamination Detection and Measurement at Entry Points

Project title	External Contamina	ation Detection and Measure	ment at Entry Points		
Project Engineer	John Harris				
Description of project	devices, that would points to the NTS the capability of	provide recommendations of the required to detect liquid gas transmission system. Th such devices to provide qu rder of magnitude" as a level	contamination at the entry e project will also evaluate uantitative measurements,		
Expenditure for financial year	Internal £6k External £607k Total £613k	Expenditure in previous (IFI) financial years	£0		
Total project costs (collaborative + external + internal)	£732k	Projected 2009/10 costs for National Grid	£124k		
Technological area and/or issue addressed by project	with regard to "solid operation of pipes 2(1) of the Gas S	GS(M)R and National Grid d or liquid material that may in or any gas appliance within Safety (Installation and Use) asonably be expected to open	the meaning of regulation Regulations 1998 that a		
	the NTS, some of either NG (compre	e several serious incidents of which have caused damag ssors) or large industrial cus compensate customers is in	e to equipment owned by tomers. The annual bill to		
	There are two main suspected mechanisms for liquid contamination:				
	1. Gas producers may accidentally allow liquids produced by process failures to contaminate the gas. Such liquids are glycols, methanol and gas condensates.				
	2. Gas that enters the NTS in compliance with GS(M)R may have a composition which, when certain physical conditions such as temperature, pressure and flow are changed, condenses out as liquid in an unexpected manner.				
		urrently used to monitor the ne following limitations:	e gas composition at NTS		
	a) All sample points and measuring instruments are designed to sample and analyse dry gas. Any liquid contamination picked up by the sample probe causes damage to the analysers.				
	b) There are no instruments in place to monitor the concentrations of some potential liquid contaminants (glycols and methanol).				
	c) The instruments which monitor higher hydrocarbon concentration and calculate hydrocarbon dew-point do not analyse on a continuous basis; a typical time interval for sampling is every 30 minutes. This may be too infrequent to detect a liquid event.				
	The photograph be pigging of Feeder 1	low shows liquid contaminati I near Paull.	on found during the routine		

<caption></caption>						
		Project Benefits Rating	Proje Residua		Overall Project Score	
Type(s) of innovation involved	Significant —	16	0		16	
Expected benefits of project	 Compliance: As a gas transporter, National Grid is responsible for ensuring that the gas they supply complies with GS(M)R. Financial: a) If gas supplied directly by National Grid is proved to cause damage to customer's equipment, then National Grid are liable for compensation. b) NTS equipment is designed to operate or monitor dry gas. Contamination of the gas by liquids causes major damage to 					
	 expensive items such as compressors. c) Whenever liquid events are discovered, they must be resolved immediately by diverting staff from their usual duties. 3) Knowledge: 					
	If a liquid eve	ent is caused by a gas v either terminating ga				
Expected timescale of project	2 years	Duration of bene achieved	efit once	10+ ye	ars	
Probability of success	60%	Project NPV = (PV – PV costs) x prot success		£1.2m		



Potential for achieving expected benefits The work up to the end of the year concentrated on establishing and proving the test rig. However, the potential for achieving the expected benefits remains good, due to the number of techniques being evaluated. Project progress A test toop has been built at the Spadeadam Test Site run by GL Industrial Services. A schematic is shown below. Googl Fig 2 – Diagrammatic Representation of Proposed Layout Image: the test intermention of the test intermention intermediate of the test intermention of the test intermention of the test intermediate of the test intest intermediate of the test intermediate of the test intermediate							
[Year to End of March 2009] Fig 2 – Diagrammatic Representation of Proposed Layout Fig 2 – Diagrammatic Representation of Proposed Layout Vert Corromatograph The test loop is pressurised with natural gas and liquids under investigation are injected via a spray nozzle capable of forming aerosols down to 1 μ in size. The photograph below shows the spray nozzle injecting octane into the test loop.	Potential for achieving expected benefits	proving the test rig. However, the potential for achieving the expected					
Fig 2 – Diagrammatic Representation of Proposed Layout Vert Othomatograph Location Vert Used tripecton Vert Instrumentation The test loop is pressurised with natural gas and liquids under investigation are injected via a spray nozzle capable of forming aerosols down to 1µ in size. The photograph below shows the spray nozzle injecting octane into the test loop.	[Year to End of March						
	2009]	$\begin{array}{c} & \\ & \\ & \\ & \\ & \\ & \\ & \\ & \\ & \\ & $					

	the second secon
AT INTE	- No

	The gas conditions inside the loop can be controlled to simulate thos found in the NTS; gas pressure up to 100bar and velocity up to 15sm ³ s. The first set of experiments will test the performance of the multi-detect instrument currently installed at NTS entry points. Ultra-sonic meters we also be tested. Preliminary experiments to establish that the test loop ar spray nozzle operates as expected are underway.					
	New Instrumentation:					
	In the absence of an "off-the shelf" analyser which can analyse gas components in gas, aerosol and liquid form, a project has been set up between GL Industrial Services and IMA Ltd., a supplier of laser based analytical instruments. The modelling of a photon counting Raman spectrometer suitable for detecting the presence of aerosols and the concentrations of gas phase methanol, MEG, TEG and benzene (to identify gas condensate) has been completed. The modelling showed that a very complex scanning spectrometer would be required to detect all four components whilst still in the gas phase, since the concentrations of gaseous TEG are extremely low. A relatively simple dichroic system would be able to analyse for the presence of aerosols in addition to benzene and methanol at gas phase concentrations. The compromise is that MEG and TEG would only be detected at concentrations at which aerosols have already formed.					
Collaborative partners	None.					
R&D provider	GL Industrial Services (UK) Ltd					





2) Research into Connections to X80 Grade Pipeline Material

Project title	X80 Hot Tap				
	 Mechanical Testing of X80 Hot Tap Circumferential Fillet Weld 				
Project Engineer	Richard Wilkinson				
Description of project	This programme area	a covers two B&D r	nroiects		
	The first project ad repairs, diversions ar	dresses the devel	opment	t of weldir	ng procedures for
	The second project affected zones of pip				
Expenditure for financial year	Internal £10k External £92k Total £102k	Expenditure previous financial years	in (IFI) 9	£158k	
Total project costs (collaborative + external + internal)	£267k		9/10 ional	£15k	
Technological area and/or issue addressed by project	The first project was commissioned in response to the increasing use of X80 pipelines and the increasing likelihood that National Grid will be required to carry out a 'hot tap' (a connection that is made while the pipeline is in service) on X80 pipe. A 'hot tap' may be required in order to maintain supplies or to connect a third party to the National Transmission System under license condition 4B of the Public Gas Transporters License.				
	The second project available for fusion I using low hydrogen information available P460NL1 high stren down electrodes.	ine toughness of w n, basic vertical e was for fusion l	velds m down line tou	ade on gr consumat ughness o	ade X80 pipelines bles. The closest f welds made on
	The first project proc could be investigat mechanical test prog fusion line toughness	ed in the secon gramme of these v	id proje velds to	ect, which	n involved a full
_ /		Project Benefits Rating		roject Jual Risk	Overall Project Score
Type(s) of innovation involved	Incremental	7 to 9	1	to -3	8 to 10
	The expected benefits of the projects were:-				
Expected benefits of	• Ensure all 'under pressure' connections are undertaken in a safe manner.				
project	• Ensure National Grid complies with it's obligations under license condition 4B with regards third party connections.				
	• Unless the 'hot tap' welding approach for X80 is validated, shut down of pipelines may be required to facilitate connections.				
	• Ensure compliance with statutory requirements i.e. Pipeline Safety Regulations 1996.				



			1		
	 Ensure technical specifications are robust for the full range of pipeline diameters and material grades. Additionally, the results of the second project will provide NG with indicative weld mechanical properties obtained from the X80 'hot tap' welding procedure. This information can be used for analysis of future X80 'hot tap' welds and offer improved confidence in the welding procedure. 				
Expected timescale of project	4 years	Duration of benefit once achieved	10 years		
Probability of success	80%	Project NPV = (PV benefits – PV costs) x probability of success	£61k		
Potential for achieving expected benefits	being commissioned to		a further piece of work is oblems with the material		
Project progress [Year to End of March 2009]	Work on the simulated (CTS) has been comple		lled thermal severity tests		
	Eiguro 1	I - Simulated P9 Weld at o	omplotion		
	high hardness values o observed in the weld.	n the fitting side weld toe,	ng of the welds indicated although no cracking was also revealed some low e X80 pipe.		
	of X80 pipelines. Reco include welding proce	mmendations on the upc dures for X80 were pro	dures for 'hot tap' welding late of P9 specification to ovided. However, it was ould be undertaken first to		

	reduce the high hardness values observed, whilst the significance of the isolated low toughness values should also be assessed. This was the purpose of the second project.
	The second project to undertake mechanical testing of the X80 'hot tap' weld has been completed and a report has been issued.
	The results were compared with P2 requirements, so they could be quantified. However, it should be noted that P2 requirements do not necessarily apply to 'hot tap' welds.
	The key findings of the test programme were:
	 Low impact values on the pipe's heat affected zone
	High hardness values on the pipe fitting weld toe.
	The project will now investigate the cause of the low impact results and develop weld procedures to reduce the hardness values.
Collaborative partners	None
R&D provider	GL Industrial Services (UK) Ltd





3) Effects of Higher Hydrocarbon Content on the Safety of Natural Gas Transmission

Project title	Effects of Higher Hydrocarbon Content on the Safety of Natural Gas Transmission					
Project Engineer	Dave McCollum					
Description of project			gas with higher hy nes and other safe	ydrocarbon content has ty risks.		
Expenditure for financial year	Internal £5k External £8k Total £13k		ture in previous ancial years	£3k		
Total project costs (collaborative + external + internal)	£16k		ed 2009/10 costs onal Grid	£0		
Technological area and/or issue addressed by project	gas transmission example importe contain greater p	system is d Liquified roportions o	coming from non- Natural Gas (LNG f higher order hyd	orted by the UK national traditional sources, for a). These sources can lrocarbons (methane is a second order etc).		
	This project addresses how gas compositions with a greater proportion of higher order hydrocarbons could impact the safety risks associated with gas transmission pipelines. For example, which pipelines could be adversely affected by these gas compositions in terms of ductile fracture propagation? Also, what is the effect on lower flammable limit, safety distances, zoning and thermal radiation levels on safety modelling of pipelines and above ground facilities?					
Type(s) of innovation involved	Incremental	Project Benefits Rating 10	Project Residual Risk 3	Overall Project Score 7		
Expected benefits of project	To allow National Grid to understand the safety risk implications of transporting gas derived from LNG and to manage the risks appropriately. For example:					
	 Avoiding long running fractures on failure (a failure situation that is not identified in National Grid's current safety case). Such events could trigger fines of £15m+ and associated costs would be at least as much again. 					
	2. Avoiding losses in transportation costs through long repair times and loss of strategic import capability.					
	 Avoiding reputation damage of not being aware of the impact on National Grid's risk profile for this change in the operating environment. 					
	By knowing which pipelines are potentially affected by the higher hydrocarbon content expected in future sources of natural gas, decisions can be made on the possible installation of crack arresters).					



Expected timescale of project	3 years	Duration of benefit once achieved	5+ years		
Probability of success	80%	Project NPV = (PV benefits – PV costs) x probability of success	£140k		
Potential for achieving expected benefits	needs to be		nformation that National Grid e various areas of risk which ons of higher hydrocarbons.		
Project progress [Year to End of March 2009]	A methodology for assessing the risks from low toughness pipelines has been developed and applied to assess the risks associated with Feeder 5. The assessed risks for low toughness and normal toughness pipelines have been used to investigate feasibility of using crack arrestors to manage risks on low toughness pipelines. Work is ongoing but work done so far indicates that costs associated with installing crack arrestors would be disproportionate to any risk reduction achieved.				
	The project is scheduled to continue with work to address the other safety risks relating to lower flammable limit, safety distances, zoning and thermal radiation levels and how these affect the safety modelling of pipelines and above ground facilities.				
Collaborative partners	None				
R&D provider	GL Industrial Services (UK) Ltd				





4) Detection & Management of Corrosion

Project title					
	 Detection & Management of Corrosion on Above Ground Insulated Pipework and Pipe Supports 				
	Above Ground Installation Paint Systems				
Project Engineer	Peter Martin				
Description of project	This programme are	ea consists of two mair	n projects.		
		(under insulation an	detect corrosion in difficult- d between a pipe and its		
	that does n		ection systems for pipework al of insulation materials or orts.		
		evaluation of the m system(s), established	nost applicable corrosion by the market review.		
	practices for the N	lational Grid Gas Tra s (AGIs) to minim	ns to develop new painting nsmission system's above ise the costs of future		
Expenditure for financial year	Internal £9k External £78k Total £87k	Expenditure in previous (IFI) financial years	£0		
Total project costs (collaborative + external + internal)	£291k	Projected 2009/10 costs for National Grid	£137k		
Technological area and/or issue addressed by project	pipework on above and be hidden under and its mechanical insulation cladding a prohibitively expens corrosion is identifier locate areas of history	ground facilities. Exte er noise insulation cla supports. Complete and pipe supports to a sive. Sample removal ed. Therefore, alternati	project is the condition of ernal corrosion can develop adding or between the pipe removal and refitting of all allow thorough inspection is does not guarantee that all ve methods are required to out removal of insulation		
	It has also become clear to National Grid that unless action is taken to improve the corrosion management of AGI assets, there will be a significant increase in repair/replacement costs and the potential for corrosion related failures.				
	A second project has therefore been instigated on the development of National Grid's painting policy and practices for its above ground installations to minimise the cost of maintenance painting.				
	This objective of the second project will be achieved by two developments:				
	perform location the requirer	al patch repair on exis	systems that can be used to sting paint coatings without and will provide temporary uled maintenance paining		





	programme.					
	Identification of over-coating paint systems which can be applied to entire sites to extend the life of the existing coating. This will mitigate having to grit-blast pipe work and structures back to bare metal and re-apply a complete paint system.					
Type(a) of innervation involved	Tech Transfer	Project Benefits Rating	Project Re Risl		Overall Project Score	
Type(s) of innovation involved	Transier	10 to 13	2 to -	-1	11	
Expected benefits of project	It is expecte number of wa	d that the first proj	ect, will be	enefit Na	itional Grid in a	
	1. Non-invasive inspection techniques will allow 100 coverage of assets, resulting in improved confidence above ground pipework integrity and identification problem corrosion prior to failures (and their associate impacts on safety, security of supply and thenvironment)					
	2. Invasive maintenance can be targeted only where it is needed, leading to a faster conclusion to remedial action programmes, followed by reduced maintenance costs in the future.					
	 National Grid can demonstrate to the Certifying Authority (HSE) that they are using the best available technology to improve safety on AGI sites. 					
	equipment a	ed that the second nd a pro-active ap iver financial benefit	proach to			
		Reduced un-schedule lue to corrosion relat		e reductio	ons and outages	
	2. F	Reduced repair costs				
	3. N	Aximisation of asset	t life			
Expected timescale of project	3 years Duration of benefit once 10+ years achieved					
Probability of success	60% Project NPV = (PV benefits – PV costs) x £65k probability of success					
Potential for achieving expected benefits	The projects to detect hidden corrosion and manage the costs of dealing with corrosion are both evaluating a large number of techniques that could be applied. This will improve the chances of finding solutions that work.					



Project progress	
[Year to End of March 2009]	The market review of corrosion inspection systems for the first project has been successfully completed and reported. The study considered a total of 17 inspection techniques that are currently being used by other industry sectors (including offshore and petrochemical) for corrosion detection, where access is difficult. These included the use of thermal imaging to literally detect "hot- spots" of corrosion under the insulation cladding and the use of a circumferential ultrasound scanner system to detect corrosion at pipe supports.
	Fig 1 - Circumferential ultrasound scanner system
	Of the 17 techniques considered, nine were considered suitable for further evaluation by pilot trials on National Grid sites, where their ability to detect corrosion, without having to remove the insulation material or dismantle the pipe supports, will be assessed.
	The inspection equipment to perform the shortlist of techniques will be hired in and used to conduct trial inspections of selected pipework systems on a number of different National Grid above ground facilities. The inspection results will be analysed and, where corrosion is indicated, the pipework will be examined further to confirm whether corrosion is present. A second report will be complied on the results of the site trials.
	On the second project, a total of nine '2-coat' paint systems, from five paint manufacturers have been applied to a range of substrates and subjected to a suite of accelerated corrosion tests. The application characteristics of these paint systems, the compatibility with coatings likely to have been previously applied to National Grid sites, and their long term performance in a range of accelerated corrosion tests have all been assessed. The materials will be ranked and suitable systems will be identified for large-scale site application trials.
Collaborative partners	None
R&D provider	GL Industrial Services (UK) Ltd



5) <u>Pipeline Fatigue Factors and Pipeline Repair Techniques</u>

Project title	Line Pipe Integr	ity (Small Drilled Hole	s)
	 Pipeline Repairs 	•	5)
Project Environ		5 F I I	
Project Engineer	Rob Bood		
Description of project	This programme of	work consists of two n	nain projects.
	with calibrated part	t-through-wall drilled	n X80 pipe spool assembly holes, simulating malicious st involved with this project
	 Pressure te 	sts	
	 Pressure cy 	cling fatigue testing	
	 Post-test m 	etallurgical assessme	nt
	the behaviour of de		o understand differences in X80 ring test samples, with pipelines.
Expenditure for financial year	Internal £8k External £52k Total £60k	Expenditure in previous (IFI) financial years	£4k
Total project costs (collaborative + external + internal)	£144k	Projected 2009/10 costs for National Grid	£79k
Technological area and/or issue addressed by project	of small drilled pa		essment of the significance d following an incident of eline.
	recommendation fo that any defect tha smooth dent, shall This could result in	r pipelines constructed t is thought to be, or be assessed by an	ioned because the current d from grade X80 linepipe is has been categorised as a expert in pipeline integrity. assess relatively minor pipe activity
	tests with smooth of axial cracking were the suitability of the limits for X80 grad specimen denting ri	dent damage where lo observed. The test re ring tension specimer e pipelines, and the a	on the results of ring tension ow failure pressures and/or esults raised questions over n to define dent acceptance appropriateness of the ring hat suitably represent those line.
	in and around dents and pipe sections a the ring/pipe diam	s of comparable type a nd quantifying the diffe eter and/or wall thick merical study, with ref	ng the stresses and strains and depth in ring specimens erences between the two as kness is varied. The work ference to the experimental

nationalgrid

The power of action.



Type(s) of innovation involved	Significant	Project Benefits Rating 11 to 15	Proje Residua 2 to	ıl Risk	Overall Project Score 13 to 15
Expected benefits of project	part wall holes o leave remaining fatigue life. The f intended to valid	ct, finite element a f up to 10mm diar ligaments of just ull-scale tests unde date this conclusi ll not have to re	meter in a Imm and s ertaken du on. If the	pipeline still retai ring the project	e can extend to in an adequate first project are is successful,
	are tolerant to observations from this not to be the dent acceptance P11 document. It scale tests on lin of the ring spe	ect aims to demo a certain amoun n dented ring expa case. The work its limits to be pres is expected that t e-pipe with smoot cimen denting rig ore realistic dent d	t of dent ansion test self will not cribed and his will be n dent dan g to enab	damag specim t be suff d incorp done vi nage an	e, despite the ens suggesting icient to enable orated into the a follow on full- d/or a redesign
Expected timescale of project	4 years	Duration of ber achieved	nefit once	10+ ye	ars
Probability of success	60%	Project NPV benefits – PV probability of su	costs) x	-£53k	
Potential for achieving expected benefits	drilled holes are pipeline. Howev locations of any can be monitore second project ha	s undertaken for t unlikely to pose a er, further work other similar sabo d over time. There as at least demons d be re-designed	threat to the is require tage can is also a trated that	the integ d to en be dete good c the X80	grity of the X80 hsure that the cted, so that it chance that the oring specimen



For the first project, a 48 inch diameter test vessel was constructed that contained a total of 24 drilled holes of 3mm, 5mm and 10mm


diameter. These drilled holes were situated both internally and

Project progress

[Year to End of March 2009]

externally and were of varying depths. The vessel was subjected to a 24 hour hydrostatic pressure test at 149barg to simulate the commissioning hydrostatic pressure test. The vessel was then subject to a 150,000 cycle fatigue test, cycling between 64barg and 94barg. The vessel completed both tests without any of the drilled holes failing. Following the completion of the above tests, the vessel was sectioned to allow a selection of the drilled holes to undergo metallurgical analysis. Fig 1 - The "drilled holes" test vessel during the tests. The "drilled holes" test vessel during the tests. Fig 2 – Selection of external drilled holes on the test vessel.





The numerical study has shown that the maximum plastic strain experienced in a model of a ring test specimen is greater than that experienced in a model of the corresponding line-pipe. This deviation appears to increase with as pipe diameter increases and it also appears to increase with dent depth. The effect of increasing wall thickness in the models was found to be small.

Fig 3 - Modelling of a 5% indentation in a 48" diameter pipe

		19-405 612-405 53-405 53-405 53-405 612-405 61	
	The potential next steps under co	onsideration are:	
	damage introduced for a give	men denting rig to ensure that the en dent depth is independent of pipe entative of that which would be	
	Full scale tests on X80 line- that is offered by conservative	pipe to determine the safety margin e ring test specimen results.	
Collaborative partners	None		
R&D provider	GL Industrial Services (UK) Ltd		
			1



6) <u>Research into the Potential for Vegetation to Damage Transmission Pipelines</u>

Project title	Assessment of the Transmission Pipelin		Vegetation to	Damage Gas
Project Engineer	Joanne Harris			
Description of project	Research the potent in gas transmission p the integrity of the pi	pipeline corridors,		
Expenditure for financial year	Internal £4k External £5k Total £9k	Expenditure previous (financial years	in (IFI) £0	
Total project costs (collaborative + external + internal)	£9k	Projected 2009 costs for Nation Grid		
Technological area and/or issue addressed by project	 Undertake a revier root or other vege Determine if it is assessment when alternative to eas If appropriate, likelihood of pipel for ranges of pip distance from thappropriate to car 	er, over time, it is p orridor. Maintainin is an expensi Therefore Nationa ion on the pip genuine concern the damage mechar ipelines. We to assess how d managed by othe ew of failure data the tetation damage to appropriate to car re there is eviden ement clearance. perform enginee line failure via the peline diameters, on the pipeline. (Note rry out this part of to summarise the	possible for trees of the pipeline c ve proposition I Grid needs to u belines to und to the ongoing i hisms from the the potential three er pipeline operation o assess if there high pressure pipery out any form ce of vegetation erring calculation credible damage depths of cover, e: it was not d the project) findings.	and shrubs to orridor free of which takes understand the erstand what ntegrity of the interaction of eat to pipelines tors. is evidence of pelines. of generic risk growth as an as to assess e mechanisms tree type and leemed to be
Type(s) of innovation involved	Incremental	Project Benefits Rating 12	Project Residual Risk -4	Overall Project Score 16



Expected benefits of project	and failure mechanism pipeline network. This	National Grid to unders as which vegetation gro s information will enal erations in relation to	wth can have on the ble National Grid to
Expected timescale of project	1 year	Duration of benefit once achieved	5+ years
Probability of success	80%	Project NPV = (PV benefits – PV costs) x probability of success	-£9k
Potential for achieving expected benefits		bleted and the benefits assessment where there	
Project progress	Final report delivered M	1arch 2009.	
[Year to End of March 2009]	transmission pipelines integrity. There does no roots would damage where the coating is in go on to undertake go However, it was recom	hat vegetation growing does not pose a signific of appear to be a mecha deeply buried steel ga good condition. Therefor eneric calculations for of mended that site-speci- by-case basis, if there	cant threat to pipeline nism whereby the tree is transmission pipes ore, the project did not damage mechanisms. fic analysis should be
	Fig 1 – A young tree gr	owing directly over a gas	s pipeline:
Colleborative northere			
Collaborative partners	None		
R&D provider	GL Industrial Services	(UK) Ltd	



7) Software Tools for Hazard and Risk Assessment of Major Hazard Gas Pipelines

Project title	00050		
	ORDER		
	PIPESAFE		
Project Engineer	Dave McCollum		
Description of project	This programme area	consists of two project	sts.
	ground installations.		nent of safety risks on above development of models and R' collaboration.
	databases for the r pipelines. This invol	nanagement of safe	nts to software and associated ty risks on gas transmission it of models and procedures ' collaboration.
Expenditure for financial year	Internal £18k External £20k Total £38k	Expenditure in previous (IFI) financial years	£74k
Total project costs (collaborative + external + internal) Technological area	£160k	Projected 2009/10 costs for National Grid	£47k
and/or issue addressed by project	etc.) associated with present potential ma event of accidental r Under the Pipeline National Grid is requi effectively, and to be level which is ALAF	h high pressure natu jor hazards (i.e. fires eleases of gas, due t Safety Regulations a red to manage the rist able to demonstrate to	compressor stations, terminals, ral gas transmission pipelines or explosions) in the unlikely to a range of potential causes. and the COMAH Regulations, ks associated with these assets of HSE that risk is managed to a sonably Practicable). The first his.
	Fig 1 – Abov	ve ground plant on a N	IG compressor station

	High pressure natura hazards (i.e. fires) in to a range of cause third parties. Under required to manage to be able to demon ALARP (As Low As help National Grid ac	the unlikely even s, but particularly the Pipeline Sa the risks associate strate to HSE that Reasonably Pract	t of accio accident fety Reg ed with th risk is m	dental re al inter julations lese as nanageo	eleases of gas, due ference damage by s, National Grid is sets effectively, and d to a level which is
	Fig 2 – Ga	as transmission pi	peline un	der con	struction
Type(s) of innovation involved		Project Benefits Rating	Proje Resid		Overall Project Score
	Significant	9	Ris 0	k	9
Expected benefits of	This projects support	National Grid in:	<u> </u>		
project	 Optimising the saddesign, and in ad effectiveness of t high pressure gas Achieving ongoing 	afety of new facilit chieving ongoing i he management o transmission pipe g improvements ir	improven of risk as line netwon the efficent	nents in sociate vork. ciency a	oropriate layout and the efficiency and d with AGIs on the and effectiveness of are gas transmission
Expected timescale of project	5 years	Duration of once achieved		10+ ye	ears



Decksbilling for		Drainet NDV (D) (1
Probability of success	60%	Project NPV = (PV benefits – PV costs) x probability of success	£54k
Potential for achieving expected benefits	Grid is able to partie	cipate in, and benefit tice in risk management,	ssion companies, National from, the development of with has more opportunity
Project progress [Year to End of March 2009]	project has been take predict the risks at co designed to be easy to been simplified in a ne the correct 'release so site. Output is produce by the program to pr	en and developed speci mpressor sites and AGI to use. The procedure f ew user interface. The r cenarios' to consider base ed in the form of a database oduce pictures and tab	of the ORDER collaborative fically for National Grid to s. The software has been or specifying the sites has model automatically selects sed on a description of the ase that can be interrogated les of use in reports. The ure of the risks from the
	have enabled the meth and updated guidance	ods for modelling explos	h the ORDER collaboration ions at AGIs to be reviewed uidance should allow the ess experienced user.
	Fig 3 – Effect of a ho	rizontal jet fire on adjace	nt above ground pipework
	number of improvem software, including th conditions in more de predicting pipeline failu	ents and extensions to le ability to take into etail and the inclusion	and issued, incorporating a the functionality of the account possible weather of an updated model for rd party damage. A number ed out including:
	PIPESAFE and pub	lished at the Internationa	probability (implemented in I Pipeline Conference). ling the effect of valves in
		i methodology for hand	ing the effect of valves III



	r
	pipeline risk assessments (to provide guidance for risk assessors using PIPESAFE).
	• Uncertainty and sensitivity analysis (to provide guidance for risk assessors using PIPESAFE).
	• Development of a mathematical model to predict the dispersion behaviour of un-ignited pipeline rupture releases (implemented in PIPESAFE).
	 Initial development of a methodology for handling long-running fractures in low toughness pipelines (ongoing).
	Review and refinement of modelling of initial highly transient behaviour immediately following a pipeline rupture failure (ongoing).
Collaborative partners	Collaborative partners for the "ORDER" group include (but are not limited to) GDF SUEZ (France), Gasunie (Netherlands), Enagas (Spain), Energinet.dk (Denmark) and Fluxys (Belgium).
	Collaborative partners for the "PIPESAFE" group include (but not limited to) National Grid (UK), Energinet.dk (Denmark), Enagas (Spain), Fluxys (Belgium), Gasunie (Netherlands), StatoilHydro (Norway) and TransCanada PipeLines (Canada).
R&D provider	GL Industrial Services (UK) Ltd





8) <u>Pipeline Inspection Techniques</u>

Project title	On-Line Inspection	on Intervals Review	N		
		Intervals Methodo		Schedu	ling of In-Line
Project Engineer	Joanne Harris				
Description of project	Trial implementation using a number of ca		spection	Interval	s specification
Expenditure for financial year	Internal £14k External £52k Total £66k	Expenditure previous (financial years	in (IFI) £1 :	3k	
Total project costs (collaborative + external + internal)	£79k	Projected 2009 costs for Natio Grid			
Technological area and/or issue addressed by project	Research into the inspection intervals f appropriate risk-bas designed to look a together with its impa	or in line inspectio ed model is use t the practicalities	n of pipe d. This s of appl	lines to stage o lying the	ensure that an f the work is
Type(s) of innovation	Incremental	Project Benefits Rating	Proj Residua	al Risk	Overall Project Score
		9 to 14	-2 to	0-3	12 to 16
Expected benefits of project	The risk-based mod take into account m asset. The use of a frequencies of som policy. This stage of give an insight into the available data an can be rolled out acr	naintenance histor a risk based mode e inspections, bu the work will prove the work required nd the new model.	y and th al may ha t will en e the vali to asses It is antio	e perfor ave an sure co dity of th ss each cipated t	mance of the impact on the mpliance with the tool and will pipeline using
Expected timescale of project	3 years	Duration of once achieved		5+ yea	rs
Probability of success	60%	Project NPV benefits – PV probability of s	costs) x	£392k	
Potential for achieving expected benefits	National Grid is con successful conclusion mitigate some of the	on. The addition			



Project progress [Year to End of March 2009] • The new model is capable of being used for planning the National Grid OL11 programme on a rational risk/reliability basis, but had a considerable impact on the frequencies of some pipelines. • Most of the data required in order to implement the recommended model was found to be available. Although there were issues when relaying this back to the specification developed in an earlier stage of the project. • Improved record management practices for On Line Inspection data and repairs were recommended in order to implement risk/reliability-based scheduling. This was an area of concern as the project was requested to address the issue of missing historical data. • Future corrosion growth rates were confirmed as a critical parameter in the model. Recommendations were made regarding the suitability of the currently applied distributions to ensure that they continue to provide an accurate reflection of pipe condition. • The model did not provide the flexibility to be able to assess what if scenarios – e.g. what would happen it the CP system was improved? What would happen to the frequencies? This would be a bespoke run overnight by a service provider. A potential conflict of interest arose from GL being the supplier of the new OLI scheduling software, whilst also being the technical authority, responsible for approving the methodology. The project became driven by the requirement to implement a software solution and not to deliver a methodology/model. National Grid therefore decided to seek another supplier in order to gain independence.
 The new model is capable of being used for planning the National Grid OL11 programme on a rational risk/reliability basis, but had a considerable impact on the frequencies of some pipelines. Most of the data required in order to implement the recommended model was found to be available. Although there were issues when relaying this back to the specification developed in an earlier stage of the project. Improved record management practices for On Line Inspection data and repairs were recommended in order to implement risk/reliability-based scheduling. This was an area of concern as the project was requested to address the issue of missing historical data. Future corrosion growth rates were confirmed as a critical parameter in the model. Recommendations were made regarding the suitability of the currently applied distributions to ensure that they continue to provide an accurate reflection of pipe condition. The model did not provide the flexibility to be able to assess what if scenarios – e.g. what would happen if the CP system was improved? What would happen to the frequencies? This would be a bespoke run overnight by a service provider. A potential conflict of interest arose from GL being the supplier of the new OLI scheduling software, whilst also being the supplier of the new OLI scheduling software, whilst also being the technical authority, responsible for approving the methodology. The project became driven by the requirement to implement a software solution and not to deliver a methodology/model. National Grid therefore decided to seek another supplier in order to gain independence.
 model was found to be available. Although there were issues when relaying this back to the specification developed in an earlier stage of the project. Improved record management practices for On Line Inspection data and repairs were recommended in order to implement risk/reliability-based scheduling. This was an area of concern as the project was requested to address the issue of missing historical data. Future corrosion growth rates were confirmed as a critical parameter in the model. Recommendations were made regarding the suitability of the currently applied distributions to ensure that they continue to provide an accurate reflection of pipe condition. The model did not provide the flexibility to be able to assess what if scenarios – e.g. what would happen if the CP system was improved? What would happen to the frequencies? This would be a bespoke run overnight by a service provider. A potential conflict of interest arose from GL being the supplier of the new OLI scheduling software, whilst also being the technical authority, responsible for approving the methodology. The project became driven by the requirement to implement a software solution and not to deliver a methodology/model. National Grid therefore decided to seek another supplier in order to gain independence.
 data and repairs were recommended in order to implement risk/reliability-based scheduling. This was an area of concern as the project was requested to address the issue of missing historical data. Future corrosion growth rates were confirmed as a critical parameter in the model. Recommendations were made regarding the suitability of the currently applied distributions to ensure that they continue to provide an accurate reflection of pipe condition. The model did not provide the flexibility to be able to assess what if scenarios – e.g. what would happen if the CP system was improved? What would happen to the frequencies? This would be a bespoke run overnight by a service provider. A potential conflict of interest arose from GL being the supplier of the new OLI scheduling software, whilst also being the technical authority, responsible for approving the methodology. The project became driven by the requirement to implement a software solution and not to deliver a methodology/model. National Grid therefore decided to seek another supplier in order to gain independence. PB Rune is now working towards the completion of this project. At the end of the year, they had completed a review and description of the existing corrosion model
 parameter in the model. Recommendations were made regarding the suitability of the currently applied distributions to ensure that they continue to provide an accurate reflection of pipe condition. The model did not provide the flexibility to be able to assess what if scenarios – e.g. what would happen if the CP system was improved? What would happen to the frequencies? This would be a bespoke run overnight by a service provider. A potential conflict of interest arose from GL being the supplier of the new OLI scheduling software, whilst also being the technical authority, responsible for approving the methodology. The project became driven by the requirement to implement a software solution and not to deliver a methodology/model. National Grid therefore decided to seek another supplier in order to gain independence. PB Rune is now working towards the completion of this project. At the end of the year, they had completed a review and description of the existing corrosion model
 scenarios – e.g. what would happen if the CP system was improved? What would happen to the frequencies? This would be a bespoke run overnight by a service provider. A potential conflict of interest arose from GL being the supplier of the new OLI scheduling software, whilst also being the technical authority, responsible for approving the methodology. The project became driven by the requirement to implement a software solution and not to deliver a methodology/model. National Grid therefore decided to seek another supplier in order to gain independence. PB Rune is now working towards the completion of this project. At the end of the year, they had completed a review and description of the existing corrosion model
new OLI scheduling software, whilst also being the technical authority, responsible for approving the methodology. The project became driven by the requirement to implement a software solution and not to deliver a methodology/model. National Grid therefore decided to seek another supplier in order to gain independence. PB Rune is now working towards the completion of this project. At the end of the year, they had completed a review and description of the existing corrosion model
end of the year, they had completed a review and description of the existing corrosion model
Fig 1 – PIG – Pipeline Inspection Gauge
Collaborative partners None yet confirmed, but negotiations are ongoing with Gas Distribution Network operators





R&D provider	GL Industrial Services (UK) Ltd (Project 1)
	PB Rune (Project 2)





9) Use of Alternative Techniques to Reduce Third Party Interference

Project title				
	Automatic Risk-Based Handling of Plant Enquiries			
	Pipeline Impact Detection System			
	Aerial Surveillance Studies			
	Unmanned Aerial Vehicles			
Project Engineer	Phil Brewer, Aroon Parmar and Duncan Hoyle			
Description of project	Third party interference presents one of the most serious risks to the integrity of buried gas pipelines. National Grid has four projects covering this area.			
	The first project is a joint project with National Grid Electricity Transmission and National Grid Gas Distribution to develop and trial an automated web-based response service to advise developers of construction restrictions in the vicinity of National Grid energy transmission assets.			
	The second project is the evaluation of the first use of a Threatscan remote-by-satellite pipeline acoustic monitoring system for the detection of third party interference.			
	The third project is a technology update on pipeline corridor surveillance methods, other than helicopters			
	The fourth project is a joint project with National Grid Electricity Transmission to investigate whether an unmanned aerial vehicle (UAV) is capable of carrying out the same tasks as a manned helicopter. For the gas side of the business, this means observing for third party interference on NTS pipelines and undertaking TD1 surveys.			
Expenditure for financial year	Internal £26k External £52k Total £78k	Expenditure in previous (IFI) financial years	£345k	
Total project costs (collaborative + external + internal)	£479k	Projected 2009/10 costs for National Grid	£52k	
Technological area and/or issue addressed by project	The first project is evaluating whether the risk of third party interference can be reduced by automatic handling of developers' enquiries relating to critical National Grid assets. For more information, see Section 45 of the detailed reports for Electricity Transmission.			
	For the second project, the objective is to examine the feasibility of an impact detection system for transmission pipelines. GE has developed a solution which has been tested on an operational pipeline in the USA and Germany. The impact detection system will be installed on National Grid's No 7 feeder for a first-application trial.			
	The third project investigated technologies that could potentially replace or reduce the use of manned helicopter flights. Currently, all gas transmission pipelines are patrolled on a fortnightly basis using a fleet of helicopters and National Grid is concerned about the associated history of fatalities, together with the environmental			

	impact of helicopter flights and the high cost of providing the service.				
	The fourth project is a more detailed assessment of one of the techniques covered by the third project. Pilot-less surveillance drones would certainly reduce the risk of pilot fatality and environmental impact of aerial surveillance and should also reduce the cost. The questions are whether they would be permitted to fly by air traffic control; and whether they can provide effective surveillance.				
	Tech	Project Benefits Rating	Project R Ris		Overall Project Score
Type(s) of innovation involved	Transfer –	10 to 13	1 to	-6	9 to 19
Expected benefits of project	For the first project, see Section 45 of the detailed reports for Electricity Transmission.				ailed reports for
	For the second project, once the Threatscan system has been installed on No 7 feeder it will enable National Grid to identify location of plant and equipment working in close proximity to the pipeline without physical impact damage taking place. This will allow National Grid to take proactive precautionary measures to safeguard the system integrity before damage occurs.				
	For the third and fourth projects, the potential benefits of this project are to reduce fatalities, environmental impact and cost of Pipeline Surveillance. It may also be possible to improve the safety and security of the gas supply through the gas transmission system by improving the protection from Third Party Interference.				
	The basis for assessing the cost benefit of viable alternatives is that the cost of providing helicopter surveillance will be around £2m by 2012. This is before considering the value attached to the lives of helicopter crew or the reduction of carbon emissions associated with helicopter flights.				
				5+ year	Ϋ́S
Expected timescale of project	5 years	Duration of ben achieved	efit once		
Probability of success	60%	Project NPV benefits – PV probability of suc		£930k	
Potential for achieving expected benefits	This programme area includes projects which can have impacts at different stages. The first project is moving towards a successful outcome that will be of immediate use. The second project has suffered some delays in commissioning and, as a result, the system has yet to be put through its paces. The other two projects are reviewing the potential for solutions that are still some years away.				
Project progress [Year to End of March 2009]	For the first project, a pilot system is available for a trial evaluation. For more details, see Section 45 of the detailed reports for Electricity Transmission.				
	For the second project, equipment was installed at five above ground				



installations on Feeder 7 between 24th September 2008 and 23rd January 2009. The system was initialised and data transmission started on 1st February 2009. The equipment on two of the sites is powered by a combination of wind and solar power.

Fig 1 – Instrument cabinet and solar panel installation work



Fig 2 – Hydrophone installation at one of the sites







The initial set of raw shock detection data has been analysed to give an indication of GE's tuning process. The post-installation tuning process is designed to enable the system to differentiate between potential impacts from general background noise in the vicinity of each hydrophone.
The next stage of the work will involve GL undertaking an independent evaluation of the installed system performance, including a series of controlled impact tests that will demonstrate functionality of the hydrophones and GE's reporting procedure.
The third project focused on remote sensing technologies but also briefly looked at a couple of impact detection systems.
Most impact detection systems would be very expensive to retro-fit and the process of retro-fitting the sensors risks damaging the pipeline. These technologies are therefore more suitable for newly laid pipelines. They would also not report on activities some distance away from the pipeline and also some quiet activities, for example flooding and fires may not be detected at all. For these reasons, impact detection systems would not be able to fully replace the helicopter patrols.
Remote sensing technologies are more likely to be a viable alternative to helicopter patrols but it will be at least 5 to 10 years before they are ready.
Technical issues surrounding the unmanned aircraft systems will be resolved within the next few years which would allow a UAV to fly some of the pipelines. This is helped by the amount of commercial interest in UAVs at the moment and the high level of development being carried out. However, regulatory issues are likely to take much longer, possibly another decade, before a UAV would be allowed to fly a patrol in un-segregated airspace.
High Altitude Platform Systems (HAPS) are also likely to be technically ready to fly in the next few years, providing that development continues as there appears to be a lot less commercial interest in HAPS. Only a small number of organisations are carrying out any development in this area which is primarily military driven. Again, regulatory issues may prevent HAPS from flying above the UK for some time after they are technically ready.
Although all of the satellites covered by the study are commercial satellites they also play an important role providing imagery to governments, security services, etc.
These activities generally take priority over the type of commercial activity that we are interested in which means that availability could be limited.
The resolution of imagery from satellites continues to improve and current high resolution optical satellites easily meet the requirements laid down for detecting third party interference. High-resolution SAR imaging satellites also continue to improve although still falls short of the 0.5 metre image resolution requirements. It will not be until the next generation of satellite sensor technology before all of the requirements can be met for pipeline monitoring.



	The end-to-end service being offered by RapidEye comes very close to meeting the high level requirements for pipeline monitoring. However, RapidEye falls short with its limited 5 metre optical resolution and the fact that it has no SAR capability. There could be value in talking further with operators like RapidEye to help shape their next generation technology. In the meantime their current technology may provide a reasonable alternative to the traditional TD1 aerial surveys.		
	It was concluded that there was not likely to be an alternative to helicopter patrols within the next five years.		
	The fourth project picks up on the likely availability of UAV technology for pipeline surveillance within the next few years. This project is being undertaken by Qinetiq, who are familiar with the military application of UAV systems. Key issues for UAVs on pipeline monitoring applications include the fact that they can currently only fly within the visible range of their operators.		
Collaborative partners	National Grid Electricity Transmission (Project 1 & Project 4) National Grid Gas Distribution (Project 1)		
R&D provider	GL Industrial Services (UK) Ltd (Projects 1, 2 & 3) Qinetiq (Project 4)		





10) Assessment of Ground Conditions on Asset Construction and Performance

Project title	 Combined Geophysical Tool for Pipeline Routing and Risk Assessment Seismic Design Screening Procedure for Pipelines Geotechnics (Soil Restraint, Support Modelling & Pipe Strain Criteria for Pipelines and Pipework) 		
Project Engineer	Matthew Sumerling, Tony Stonehewer, Alan Hodder		
Description of project	This programme of work is designed to study how ground conditions can affect the construction of assets and how pipeline assets perform once they have been commissioned. The programme includes three projects.		
	The first project was initiated with the primary objective to trial new approaches to subsurface (geophysical) surveying, which will reduce the cost of pipeline construction projects, caused by unforeseen or avoidable sub-surface ground conditions. The project will trial these new approaches during the preparation work prior to the construction of a new gas transmission pipeline.		
	It is hoped that the project will demonstrate a cost effective method for providing detailed geological information prior to beginning site works on pipeline construction projects with the objective of establishing the optimum pipeline route.		
	Fig 1 – Examples of the type of data which could be achieved		
	Bedrock Depth Profile		
	The second project is research into international best practice on designing pipelines and other major infrastructure for earthquake resilience, with respect to the development of a new seismic design screening procedure for use during the preliminary design stage on new pipeline projects. The third project is research into soil restraint, support modelling and pipe strain criteria for pipework and installations.		



Expenditure for financial year	Internal £15k	Expenditure	ə in	
	External £41k	previous	(IFI)	£3k
	Total £56k	financial ye		
Total project costs (collaborative + external + internal)	£454k	Projected costs for Grid	2009/10 National	£352k
Technological area and/or issue addressed by project	The first project addresses how best to combine the multitude of available geophysical survey techniques on one platform meaning that one survey will provide the majority of information required for construction projects. Although multi-sensor platform technologies exist, they have not been used before in the UK energy sector. The research will examine the benefits of greater integration of geophysical data into the pipeline routing process at an earlier stage of project design.			
	The second project aims to ensure that seismic design measures are only included on new pipeline projects where they can be shown to be reasonably expected. This will ensure that a decision to not include seismic design measures on a new pipeline can be easily justified by reference to the collated information on international best practice.			
	The third project aims to develop further understanding of the dynamic behaviour and damping of buried pipework and installations, with regard to the risk of fatigue failure and associated safety hazards. The project has been initiated in response to the requirement to calculate soil restraint properties and validate the effectiveness of buried pipework and installations in reducing vibration to acceptable low levels. The results will be used to provide design guidance for incorporation into all works contracts.			
Type(s) of innovation involved	Incremental to Tech Transfer	Project Benefits Rating 9 to 14	Project Res Risk 3 to 0	idual Overall Project Score 6 to 13
			01010	
Expected benefits of project	For the first project, it is widely recognised that the use of a mobile multi-sensor platform, compared to traditional subsurface survey methods achieve cost savings of 5:1 (saving on costs of liaising with landlords and matching up disparate datasets from individual specialists). It is claimed that a corridor 2.5km x 40m could be surveyed each day with the mobile multi-sensory platform. By undertaking subsurface surveys of the soil composition before and after a pipeline is laid, National Grid has the data available to deal with (e.g. counter) any compensation claims from the landlord that the soil composition (i.e. soil type and %clay) has been changed. The development of a best practice manual, decision support tool and survey data visualisation will help to ensure that the above benefits are available for future pipeline construction projects.			
	For the second project, the expected benefit will be a screening process that will indicate that specific seismic design measures are not required in most cases of high pressure gas transmission pipelines in the UK. This could save the estimated £1m additional			

	cost of specific seismic design measures on a typical new pipeline project. It could also speed up the process of dealing with planning objections relating to seismic concerns.			
	The third project is expected to provide important design guidance for the avoidance of vibration fatigue failures on buried pipelines. This is an important part of the strategy for new builds in particular. The increased knowledge will lead to a greater understanding of buried pipeline and pipe support behaviour for more accurate analysis and a safer high-pressure pipeline system. Consequential benefits include:			
	 Increased scope for pressure up-rating of pipelines 			
	Less conservative designs on new pipeline installations			
	Reduced co	osts of assessment and moni	toring	
	Reduced costs of remediation, protection and replacement of steel pipelines			
	Maintenance	ce of pipeline safety standard	s to satisfy the HSE	
Expected timescale of project	4 years	Duration of benefit once achieved	5+ years	
Probability of success	60%	Project NPV = (PV benefits – PV costs) x probability of success	£1,000k	
Potential for achieving expected benefits	The first and second projects are still at an early stage, but are now on track. The third project should conclude during the next year.			
Project progress [Year to End of March 2009]	For the first project, lengthy contractual negotiations mean that the project is now due to start in Spring 2009. The progress achieved through 2008/2009 was to scope and assess the benefits of the project and get the necessary contracts in place.			
	For the second project,, an initial review has been undertaken of the following to identify the key documents for a detailed review:			
	 UK Codes, Guidance and Recommendations relating to seismic design. 			
	 Most of the recent Brecon-Tirley pipeline project documents, prepared as deliverables for 'seismic analysis specifications' rev 02. 			
	 US and Japanese Codes. 			
	 UK Natio 	onal seismic hazard map (BG	S).	
	 Operational issues. 			
	 Permane 	ent ground movements resulti	ng from an earthquake.	
	The third project is a continuation of the review of existing knowledge on dynamic behaviour and soil damping effect of buried pipework, finite element analysis and numerical analysis work that was completed last year. A test rig has been constructed to obtain experimental data. The test rig (sketch below), which has been			





designed and built at the Pipelines Maintenance Centre, will enable a range of conditions to be tested for main pipework and small bore connections, in the unburied and buried states. Fig 1 – Sketch of test rig 500 500 ·II---, Excavated trenc 4000 Experimental testing on the pipework in its unburied state has been completed, with a comprehensive set of data collected, measuring the response of the main pipework and two attached stabbings using hammer impacts and a vibration shaker to excite the pipework. The photograph below shows the test rig during the testing of the pipework in unburied state with the shaker mounted on the concrete plinth. Fig 2 – Testing of pipework in the unburied state The underground section of pipework was then buried and tests to determine the effect of burying on the response of the pipework should be completed by the end of May 2009. A draft report for data analyses on soil restraint calculation has been produced and work is ongoing to incorporate feedback received. **Collaborative partners** None **R&D** provider Zetica (Project 1) GL Industrial Services (UK) Ltd (Projects 2 & 3)



11) Efficient Asset Management

Project title	Demonstration of	VSD Air Compresso	r Canability to Reduce	
	Demonstration of VSD Air Compressor Capability to Reduce Energy Consumption on Compressor Stations			
	Improved Internal Flow Regime for Pipelines			
Project Engineer	Wayne Jackson & Mick	Cook		
Description of project	This programme of work aims to improve efficiency and reduce environmental impact of operating assets. To do this, two projects are looking into modification of existing assets and introduction of new technologies into existing assets.			
	generation componen		n of new compressed air rential to reduce electrical ssor stations.	
	The second project is assessing the feasibility of using of a textured surface (sharkskin effect) on the internal surface of gas transmission pipelines. A similar technology has been used to reduce drag on ships, aircraft and even swimwear. It has also been used on the internal surfaces of cardiovascular implants to improve circulation and thereby reduce the potential for clotting. The project will determine whether the technology can be realistically applied to gas transmission pipelines and, if so, the project will quantify the business benefits and associated implications.			
Expenditure for financial year	Internal £15k External £65k Total £80k	Expenditure in previous (IFI) financial years	£0	
Total project costs (collaborative + external + internal)	£92k	Projected 2009/10 costs for National Grid	£12k	
Technological area and/or issue addressed by project	The first project aims to demonstrate a significant reduction in electricity usage on a compressor station by the system that provides the compressed air supply for pneumatic valve actuators and nitrogen charging for dry gas seals on the gas process compressors. This system typically represents the largest use of electricity on a number of National Grid's compressor stations. At Nether Kellet and other similar sites, the existing selection of air compressors had been made on a lowest capital cost basis. However, these units run continuously, whether or not there is a demand for compressed air. By contrast, it is claimed that Variable Speed Drive (VSD) compressors can be configured to only run when there is a demand for compressed air.			
	system typically repre National Grid's compr sites, the existing sel lowest capital cost whether or not there i claimed that Variab	sents the largest use of essor stations. At Nethe ection of air compresso basis. However, these s a demand for compres le Speed Drive (VSD	cess compressors. This electricity on a number of rr Kellet and other similar rs had been made on a units run continuously, ssed air. By contrast, it is) compressors can be	
	system typically repre National Grid's compr sites, the existing sel lowest capital cost whether or not there i claimed that Variab configured to only run Atlas Copco, who pro Kellet, also supplies V the replacement units	sents the largest use of ressor stations. At Nether ection of air compressor basis. However, these s a demand for compres le Speed Drive (VSD when there is a demand wided the original air co /SD air compressors. Us	cess compressors. This electricity on a number of rr Kellet and other similar rs had been made on a units run continuously, ssed air. By contrast, it is) compressors can be	
	system typically repre National Grid's compr sites, the existing sel lowest capital cost whether or not there i claimed that Variab configured to only run Atlas Copco, who pro Kellet, also supplies V the replacement units familiarity with the plan The first project will th using variable speed compressor station.	sents the largest use of ressor stations. At Nether ection of air compressor basis. However, these s a demand for compress le Speed Drive (VSD when there is a demand voided the original air co /SD air compressors. Use s will reduce implement nt and its connections. rerefore aim to clearly de drive (VSD) air compre A potential saving in est	cess compressors. This electricity on a number of rr Kellet and other similar rs had been made on a units run continuously, ssed air. By contrast, it is) compressors can be for compressed air. mpressor units at Nether ing the same supplier for	
	system typically repre National Grid's compr sites, the existing sel lowest capital cost whether or not there i claimed that Variab configured to only run Atlas Copco, who pro Kellet, also supplies V the replacement units familiarity with the plan The first project will th using variable speed compressor station. A identified if the two e	sents the largest use of ressor stations. At Nether ection of air compressor basis. However, these is a demand for compress le Speed Drive (VSD when there is a demand vided the original air co /SD air compressors. Use is will reduce implement int and its connections. erefore aim to clearly de drive (VSD) air compre A potential saving in ex xisting air compressors ect, it is widely under	cess compressors. This electricity on a number of rr Kellet and other similar rs had been made on a units run continuously, sed air. By contrast, it is) compressors can be for compressed air. mpressor units at Nether ing the same supplier for ation costs, due to their monstrate the benefits of ssors on a National Grid kcess of 60% has been	

			T	
	reduces the gas wall friction also	s pressure (and a increases). Co	as the gas pressu mpressors are the	friction progressively re reduces, the pipe erefore positioned at me the effect of pipe
	reduced, with a carbon dioxide.	ssociated fuel s For new pipe	avings and reduc lines, it would b maller or less fi	or usage would be tion of emissions of be possible to give requent compressor
	internal epoxy of purpose of corr The epoxy surfa project therefore significant impro wall friction. The	coating that is a osion protection ace has a lower f e needs to demo ovement on the p e project also nee xtured surface of	pplied at the pipe between fabrication friction than that of constrate that the t plain epoxy surface eds to demonstrate	constructed with an a mill, mainly for the on and construction. the bare metal. The extured surface is a with respect to pipe that it is possible to ts primary corrosion
	it can be succes		to existing pipelin	vould be enhanced if es, as well as being
	technology wou	Id include proce	ss compressor im	the textured surface peller vane surfaces npressor blades (to
Type(s) of innovation	Tech Transfer	Project Benefits Rating	Project Residual Risk	Overall Project Score
involved		8 to 11	3 to -4	5 to 15
Expected benefits of project	For the first project, the cost of supply for two new VSD compressors from Atlas Copco (to replace one of two air compressors on each gas compressor unit) is £30,460. The electricity savings for the two VSD compressors (only running when there is a demand for compressed air) are estimated as £33,000 per year, based on 9.5p/kWhr. This will provide a useful step forward towards the company target of 80% carbon footprint reduction by 2050 – and should act as a catalyst for further energy saving suggestions from the site personnel. The VSD compressors should also last significantly longer, because they will be running for a fraction of the time that the existing compressor run (no "unloaded" running), thereby reducing maintenance costs and increasing system reliability.			
	potential benefit applied to gas National Grid ne its stated target the utilisation o	t of the technolo transmission eeds to consider of 80% carbon f compressors (n impact in the	ogy and whether i pipelines, particu some imaginative footprint reduction (fuel usage and c	s understanding the t can be realistically larly existing ones. schemes to achieve by 2050. Reducing operating life usage) and may also have



			5+ years
Expected timescale of project	2 years	Duration of benefit once achieved	
Probability of success	60%	Project NPV = (PV benefits – PV costs) x probability of success	-£15k
Potential for achieving expected benefits	identification of showing that the	further 10-15% energy say	n expected result, due to the vings. The second project is ins to be seen whether it can es.
Project progress [Year to End of March 2009]	replaced with G installation ener of the projected	A30 VSD compressor unit gy survey demonstrated th	compressor units have been ts at Nether Kellet. The post hat the result was within 1% hotograph shows one of the
		o unit installed on the comp	A 30 VSD
	associated prob	eful in keeping costs down	installation process, but the This experience and lessons on the subsequent roll-out to
	looked for ways that the original that regenerate actually needed	s to achieve further energ compressed air systems h on a timed basis, whe . Therefore, 'Purge Contro	units, the project team also y savings. They established ad been installed with dryers ther or not regeneration is I Saver' systems, which only certain dew-point, were also



procured for each compressor unit. These will save a further 10 - 15% more energy. The trial installation of the purge control savers is shown in the following photograph:

A small amount of effort is required to complete the project, but National Grid are already looking at other compressor stations to see whether the energy savings can be repeated elsewhere.

Fig 2 – Purge control unit installed on the station's air system




For the second of these projects an interim report has been produced on the feasibility of applying an internal textured surface to gas transmission pipelines. The final report is scheduled to be produced for the end of June 2009.

The key findings to date are:

- Although the study is focussing on 36" pipelines, optimum riblet dimensions (height and spacing) are not significantly affected by pipe diameter.
- $\circ~$ The optimum "L" riblet height is thought to be of the order of 1mm, with a spacing of about 0.5mm.
- $\circ\,$ Excessive feature dimensions result in flow reduction, rather than drag reduction.







12) Compressor Asset Research

Project title				
	Research into Compressor Power and Temperature Limits			
	IRIS Centrifugal Separator Trial			
	Ultrasonic Gas Leak Detection in Compressor Cabs			
Project Engineer	Tony Green, Stephen F	vickard, Dave McCollum		
Description of project	This area includes reliability and safety of	three projects focussing of compressor plant.	on the performance,	
		esearch aimed at improving that are applied to co		
		of power that is available fro ocess compressors – and ho		
		Im allowable temperature of harge pipework.	the compressor	
	The second project is an evaluation of a centrifugal separator device to remove liquids from the fuel supply lines to the gas turbine engines, which drive most of National Grid's compressors.			
		esearch into the suitability of tilated enclosures that hous		
Expenditure for financial year	Internal £23k External £24k Total £47k	Expenditure in previous (IFI) financial years	£55k	
Total project costs (collaborative + external + internal)	£131k	Projected 2009/10 costs for National Grid	£29k	
Technological area and/or issue addressed by project	The first project will d	letermine:		
	 Realistic maximum power characteristics for each different type of gas turbine used to drive gas compressors on the NTS gas transmission system where, historically, National Grid has relied on information provided by gas turbine suppliers. 			
	• The reasoning behind the discharge temperature limits that are set on each of the compressor stations. Such limits can restrict the capacity of the network under some operating conditions, so it is hoped that a better understanding of the reasons behind the limits may provide opportunities to either increase the temperature limits or reduce the process temperature.			
	contamination, desc detailed reports. The Turbine OEM's to p certain limits and it is help National Grid to	t tackles one of the con ribed in Section 1 of the ere is a mandatory requirem provide a clean, dry gas s s hoped that the centrifugal achieve this when there is li ect of liquid contamination c	e Gas Transmission nent from all the Gas supply system within separator device will quid contamination in	



	damage to gas turbine hot gas path components, resulting in loss of efficiency and increased operational, overhaul and repair costs. If the technology can be proven it could also possibly be used for gas treatment on dry gas seal systems, which is another technical problem area			
	area The third project is assessing the potential of using ultrasonic leak detection in compressor cabs to replace traditional gas detectors, which detect the quantity of gas in a gas-air mixture. According to HSE: PM84 guidance, a good ventilation system dilutes small leaks and prevents localised build-up of potentially explosive air-gas mixtures. However, the high ventilation flow rates that are typical in National Grid compressor cabs can cause excessive leak dilution, such that large gas leaks cannot be detected by traditional gas detectors. An alternative method of gas detection is therefore sought, which can detect gas leaks reliably and independently of the ventilation flow rate. The project is evaluating whether the effectiveness of ultrasonic detectors is limited by interference from the operation of rotating machinery and other systems in the enclosed operational environment.			
_ /. /		Project Benefits Rating	Project Residual Risk	Overall Project Score
Type(s) of innovation involved	Incremental To Tech Transfer	9 to 11	3 to 0	7 to 10
Expected benefits of project	For the first project, a better understanding of the power and discharge temperature limitations of compressors will lead to more realistic capital investment decisions on the potential upgrading of the existing compressor stations (for example, delayed or reduced capital costs). Alternatively, it might lead to timely capital investment (or actual changes to operating limits) to prevent future failures to deliver capacity.			
	For the second project, the result is expected to be a cost effective solution to liquid contamination of fuel gas supply systems on gas turbines. It would be an effective alternative to coalescing filters that have proven on recent site builds to be less that effective and are expensive to install/maintain.			
	For the third pro	ject, the expected	benefits are:	
	• Fewer gas detection sensors will be required to provide full coverage for the compressor cab.			
	 Potential for much smaller gas leaks (<0.1kg/s) to be detected, leading to earlier intervention. 			
			cause there are few ey can be wall-mour	
	protecti		gas turbine enclo rom overheating (by ion).	



Expected timescale of project	3 years	Duration of benefit once achieved	5+ years		
Probability of success	60%	Project NPV = (PV benefits – PV costs) x probability of success	£66k		
Potential for achieving expected benefits	understanding re work will determ of temperature started the trial provide information	et has so far produced a elating to power and temperat nine in particular whether the limits can be exploited. The of the equipment yet. The t cion to confirm the potential o been hampered by difficulties onal sites.	ture limits. The remaining improved understanding second project has not hird project continues to f ultrasonics, the pace of		
Project progress [Year to End of March 2009]	completed and National Grid. guidance build deterioration sho	ject, research into gas turbin incorporated into a guidance As well as referencing m s in practical experience, own in the following time grap	document for use within nanufacturer's data, the such as the power h.		
	applied to gas Essentially, a lir pipework protec	so been completed into the te transmission pipelines and nit of 49 – 50°C is applied to tive coatings. A couple of ex osed to excessive tempera s.	the reasons for them. prevent disbondment of amples of pipework that		
	Fig 2 – Damage caused by excess temperature				

nationalgrid The power of action.



A small amount of work remains to complete the temperature limit aspect of the project. This will review the scope to improve compressor station flexibility within the 50°C temperature limit.

For the second project, delays have been experienced in finalising the trial compressor station. Of the two sites that have been considered to date, Warrington has been undergoing a major control system re-fit; while Moffat has been running substantially less since the new Avonbridge compressor station was commissioned. It is hoped that a trial can be run next year.

For the third project, noise mapping operations have been carried out within two compressor cab designs at two different sites. These were designed to assess the following:

- Whether the ultrasonic noise regime within the running cab environment was low enough to allow the detectors to operate well.
- The number of detectors that would be required to detect a leak occurring anywhere within the cab.
- The smallest leak size detectable with the prevailing background noise

Fig 3 – Ultrasonic detector A (top right) shown in position adjacent to a gas compressor at a National Grid compressor station



Low utilisation of the compressor stations, originally selected for the field work, has led to delays on the project. Meanwhile, there is an increased interest in reviewing alternatives for the other "fire and gas" safety detection systems in compressor cabs, particularly where they are traditionally mounted in the cab ceiling area, which makes maintenance potentially hazardous. Therefore, consideration is being given to broadening the scope of this project to cover all "fire and gas" safety systems in the compressor cab.





Collaborative partners	None
R&D provider	GL Industrial Services (UK) Ltd (Projects 1 & 3) Dresser Rand (Project 2)





13) Research into Valve Life , Maintenance and Replacement

Project title				
	Ball Valve Deter	ioration		
	Ball Valve Sealant			
	Plumley Block Valve Removal			
	 Pipeline Isolatic Network 	on Philosophy for a SMA	RT Gas Transmission	
Project Engineer	Steve Johnstone			
Description of project	National Grid are un	ndertaking four projects in t	his area.	
	second 30" Cort i	esearch to establish the le solation valve, which ha ire and many more mover e first valve tested.	as experienced higher	
	components within	ct is research into the of a 42" ball valve, with re to improve maintenance.		
	The third project research into factors affecting valve condition within pits. This information will be used as evidence for helping the business to determine valve technical asset lives and updating Maintenance Policy where appropriate.			
	The fourth project is a feasibility study addressing the potential of developing an isolation philosophy for a SMART gas National Transmission System that maximises the use of new technology and the existing asset footprint, whilst maintaining reliability, minimising safety risk and improving the efficiency of network operation and maintenance.			
Expenditure for financial year	Internal £18k External £42k Total £60k	Expenditure in previous (IFI) financial years	£0	
Total project costs (collaborative + external + internal)	£142k	Projected 2009/10 costs for National Grid	£82k	
Technological area and/or issue addressed by project		ns to develop an underst ervice transmission ball va		
	The second project was commissioned in response to a number of Nuovo Pignone ball valves being removed from service at Aberdeen Compressor Station due to their poor performance in terms of pressure containment. An investigation found that the lack of sealant and the inability to inject further sealant was the underlying cause. This project seeks to determine whether old sealant can be removed in situ with the use of solvent, to allow the injection of new sealant.			
	to remove a pit-inst will allow further de installation, where evidence to the b	s been commissioned whe talled, life-expired block ver- tailed condition analysis of the output from these pusiness on Technical A s and where appropriate	alve from service. This on a typical block valve findings will provide sset Lives for valves	





	Policy.				
	Policy. The fourth project addresses the fact that the period since the mid- 1980's has seen a progressive evolution in the design recommendations for the spacing (positioning, design and installation) of isolation valves on gas transmission pipelines (IGE/TD/1), whereby the recommended separation has increased. However, the latest recommendations set out the factors that should be taken into account, but leaves development of a suitable spacing rationale to the discretion of the responsible engineer. The continued drive for operational efficiencies has reduced the number of maintenance teams which would be available to respond to emergencies and attend sites to manually isolate the flow of gas. In the event of an incident, there would be a requirement to reduce gas flows as soon as possible and it is therefore likely that remotely operable valves would be used to isolate the affected pipeline(s). However, these are only currently located at critical points in the network (e.g. multi-junctions, off-takes and compressor stations) and their operation could result in the loss of supply to a large number of Distribution Networks and/or isolation of hundreds of km of pipeline.				
		Project Benefits Rating	Project Residual Risk	Overall Project Score	
Type(s) of innovation involved	Significant	6 to 16	2 to 0	6 to 14	
Expected benefits of project	For the first project, the expected benefit is identification and development of asset deterioration measures to establish the level of current asset deterioration and enable predictions of future deterioration. For the second project, if the investigation is successful, the result will be a procedure that can be used to flush and re-inject sealant into				
	Nuovo Pignone ball valves which will eliminate the need to remove further valves from service.				
	For the third project, if an ageing block valves fail closed, it can negatively affect the security of the energy supply. If an ageing block valve fails open, it could significantly increase the severity of a pipeline failure incident. Ageing block valves are also responsible for unplanned emissions of natural gas (including 85-93% methane) into the atmosphere. National Grid therefore has to consider replacing or repairing these assets, together with models that could be used to prioritise such actions. This project will therefore develop and evaluate prioritisation models and new techniques for conducting repairs, rather than replacing them.				
	 Cost to repair this type of asset = £100k 				
	 Cost to replace this type of asset with new = £200k 66 Block valve sites in pits times the difference between 				
	repair/rep	lace (£100k) = £6.6N	l potential cost savi	ng.	
	For the fourth project, the benefit will be a better appreciation of the potential for adopting and implementing a SMART pipeline isolation philosophy, involving selective modifications to the existing pipeline isolation asset base. For example, a SMART isolation philosophy might reduce the number (and therefore the overall maintenance				





	cost) of isolation block valves that are currently maintained, while introducing advanced technologies (e.g. remote testing to further reduce maintenance costs) to take advantage of the conversion of a number of remaining isolation block valves to be remotely operable (to reduce the impact of emergency block valve closure on the security of supply).			
Expected timescale of project	3 years	Duration of benefit once achieved	10+ years	
Probability of success	60%	Project NPV = (PV benefits – PV costs) x probability of success	£407k	
Potential for achieving expected benefits		are at varying stages, but ver the expected benefits.	are all still on track and	
Project progress [Year to End of March 2009]	For the first project, a second 30" Cort valve for testing has been identified from a number removed from Wormington Compressor Station. Its selection was based on it seeing more movements and being subject to higher in service temperatures during its operational life than the Cort valve tested previously.			
	The valve has strength and lea	undergone a series of pn kage tests.	eumatic and hydrostatic	
	have been inspe sent for speciali of the mechanic	been dismantled on one si ected and assessed. The val st assessment to determine al properties of the polymer pared to new springs.	ve seal and springs were the level of degradation	
		een issued detailing the tes om the previous Cort valve ir		
			-	
	Fig 1 – 30" Cort valve under hydrostatic pressure test			
		22		

nationalgrid The power of action.



Fig 2 – Dismantling the valve after the hydrostatic pressure test



For the second project, Three 42" Nuovo Pignone valves were identified for this trial, including the valve used in the original performance investigation. Samples of residual sealant have been recovered from various locations around the ball along with samples from the sealant injection lines. These samples have been chemically analysed to identify the type of sealant used originally. They have also been subject to solubility/dispersion tests in solvent to provide an indication of whether or not the old sealant would break down sufficiently to allow fresh sealant to be injected. The polymeric valve seal has also been subject to solvent compatibility testing to ensure there are no adverse effects to its sealing capability.

The results suggest that the solvent chosen for this trial is suitable for this purpose.

The next stage is to trial the solvent in the three valves to gauge its effectiveness during a full scale test, and to develop a procedure for use on valves in service.







Fig 5 – Example of a pit valve

The fourth project is in the early data-gathering stage. An initial survey of information held at Ambergate has been completed. A search of the Institution of Gas Engineers and Managers (IGEM) archives was delayed by their office relocation.

The following photographs show a manually operated block valve installation and a remote operated block valve installation.

Fig 6 - An above-ground block valve in southern Scotland




nationalgrid

The power of action."

236









14) AGI Meter Modification to Increase Efficiency

Project title	AGI Meter Enhancement and Boiler Capability Study				
Project Engineer	John Wilson & Richard Lingard				
Description of project	Pilot demonstration upgraded to meet t future maintenance of	he requirements	of ISO516	57:2003 and red	
Expenditure for financial year	Internal £4k External £145k Total £149k	financial years	in IFI) £0		
Total project costs (collaborative + external + internal)	£149k	Projected 2009 costs for Nation Grid			
Technological area and/or issue addressed by project	This project aims to pressure offtakes, w users, can be maint limits without significa	hich supply Powe ained within requ	er Stations iired meas	and large indust	trial
	The improvements ISO5167:2003 (exist metering into line wit	ing installation wa	as ISO5167		
	The improvements will also allow gas quality and key process data, including record of validation and flow configuration, to be retained and interrogated remotely.				
Type(s) of innovation involved	Incremental	Project Benefits Rating	Projec Residual		t
		11	2	9	
Expected benefits of project	The new metering system will achieve the required (contractual) uncertainty with a significantly lower maintenance frequency (reduction of maintenance cost and associated environmental impact of travel to site) and with less potential for effort-consuming disputes over metering accuracy.				
	On the pilot implementation, the total reduction of effort could be more than 300 days/year (although the average for the 27 sites would be quite a bit lower).				
	In addition to direct technician call out costs, there could also be reductions in the costs associated with processing data for meter error reconciliations. Each meter error can typically require up to 30 man days effort for data processing and there are around 3 meter errors per year across the 27 high pressure offtake sites.				
Expected timescale of project	1 year	Duration of once achieved		5+ years	



	1		
Probability of success	80%	Project NPV = (PV benefits – PV costs) x probability of success	£40k
Potential for achieving expected benefits	installation of the me monitored to determ predictions have been	ject has been successfu tering enhancements. ine whether the ope achieved. The evaluatio unit has yet to commen	The situation will be erational expenditure n into the condition of
Project progress [Year to End of March 2009]	system benefits from i and energy uncertainti operator much higher	ogrades have been im mproved instrumentatio es considerably, giving confidence levels that and best practice proce	n which reduces flow the customer and the the system operates
	Fig 1 – New instr	umentation to meet ISO requirements	5167 & ISO5168
	data storage and new supervisory system all enable the operator to energy usage if the instrumentation or flow	provides additional bene w, approved validation ows 18 months of histo calculate much more a re were failure of an v and energy calculatio d will be implemented to 12.	capability. The new prical data storage to ccurately the flow and y of the secondary ns. This is feature is









15) Research into the Effect of Design and External Factors on Metering Assets

Project title	Orifice Plate C	Contamination CED Ma	delling ^o Motor Apost		
	Orifice Plate Contamination CFD Modelling & Meter Asset Operation				
	LDZ Installation Effects				
Project Engineer	Quentin Mabbutt, Luke	e Fieldhouse			
Description of project	This programme are	This programme area covers two R&D projects.			
	The first project is an investigation into the suitability of Computational Fluid Dynamics (CFD) modelling to assist in the assessment of measurement error in orifice plate metering systems where contamination is found. If suitable, the method will be used to assess how maintenance scheduling can be changed to reduce overall costs, while focussing on those metering installations that require cleaning to keep measurement uncertainty within acceptable limits.				
	The second project is research into suitability of CFD modelling to assist in the assessment of flow measurement bias, caused by flow disturbance (swirl and non-laminar flow) that is generated by bends and other fixtures upstream of orifice plates at metering installations. If suitable, the method will be used to assess the implications for all metering installations measuring gas flow out of National Grid Gas Transmission's network (NTS).				
Expenditure for financial year	Internal £8k External £75k Total £83k	Expenditure in previous (IFI) financial years	£0		
Total project costs (collaborative + external + internal)	£83k	Projected 2009/10 costs for National Grid	£0		
Technological area and/or issue addressed by project	The first project was commissioned to assess whether the cost of periodic calibrations and maintenance on National Grid Transmission's metering assets could be reduced. Orifice plates in gas metering systems are inspected and calibrated annually. If the effects of orifice plate contamination can be better understood, there is potential to reduce the frequency of maintenance relating to these assets, resulting in OPEX savings.				
	The latest orifice plate contamination programme using fixed and viscous contaminant has produced a comprehensive data set for future in-service contamination instances. However, there is considerable variation in actual contamination cases, such that for the existing data to be of use, it would be advantageous to be able to use a CFD type modelling technique to assist in the determination of measurement error.				
	measurement error. Some previous reconciliations have been high profile and attracted significant interest from the natural gas metering community. Contaminated orifice plates act as an early warning system for contamination of other downstream meters, which may result in large reconciliations from directly connected customers. If the CFD technique is to have applicability, it will be necessary to calibrate the				





	existing suite of CFD software with the latest experimental data.			
	The second project was commissioned to assess whether it is possible to use CFD to predict measurement bias from information on the upstream pipework configurations of the metering installations that measure gas flow out of the NTS.			
	ISO 5157:2003 sets out the method by which gas flow through orifice plate meters is calculated and the extra uncertainty that needs to be declared when upstream pipe straight length is non-compliant. A previous NEL report identified that there is potential for compliant and non-compliant orifice plate metering installations to under-register or over-register, depending on operating conditions.			
	This project will therefore use CFD to analyse all the orifice plate installations that measure gas flow from the NTS into one gas distribution network. The particular gas distribution network (or LDZ) was chosen to provide a good level of diversity of metering installations. This would allow the results to be scaled for most of the other NTS metering installations.			
		Project Benefits Rating	Project Residual Risk	Overall Project Score
Type(s) of innovation involved	Significant	12	0 to -1	12 to 13
Expected benefits of project	For the first project, the work will enable an informed view of the maintenance cycle. Clear assessment of the bias introduced to metering systems by contamination will allow swift and transparent reconciliation. These errors have a propensity to result in under0-registration, so this will lead to cost recovery.			
	Following completion of the programme, there is potential to reduce maintenance intervals at National Grid Transmission sites. National Grid Transmission operates 32 sites at present; 25 of these have a six monthly rolling validation cycle. The CFD analysis aims to allow a structured evaluation of sites where the maintenance interval could be extended to an annual visit.			
	For the second project, analysis of uncertainty associated with the topology of the pipework upstream of a metering system will be available to inform future designs of gas flow measurement installations. This will enable the design to be optimised, particularly on its footprint, which could be reduced if upstream straight lengths can be reduced below the compliance figure in ISO 5167:2003.			
	can be reduced below the compliance figure in ISO 5167:2003. ISO 5167:2003 requires the addition of 0.5% uncertainty to measurements where the upstream length is sub-compliant. However, experimental results show that the result of non-compliant upstream length is a bias, rather than uncertainty. For a "typical" site with a capacity of 1mscm/day at 2p/kWh, a 0.5% uncertainty represents about $\pm 1k/day$, which could be quantified by better understanding of the characteristics of the bias seen in the experimental results. National Grid Transmission have metering systems at 32 exit points where the capacity is between 0.15 and 6.0 Mscm/day.			



Expected timescale of project	1 year	Duration of benefit once achieved	5+ years	
Probability of success	60%	Project NPV = (PV benefits – PV costs) x probability of success	£245k	
Potential for achieving expected benefits		pject, the probability of CFD that resembled the existing %.		
	outcome to the	d project, the expectation w e project, based on the exp naller scale project in 2007-0	erience gained with the	
Project progress	For the first pro	iect:		
[Year to End of March 2009]	A report has been produced covering the results of the investigation, whereby experimental data from contaminated orifice plate tests conducted by GL Industrial Services (formerly Advantica) was reviewed by TUV-NEL against their CFD modelling and their experience of conducting related experimental work.			
	The experimental data had covered tests with clean orifice plates, orifice plates contaminated with resin and orifice plates contaminated with grease. The amount of contamination was varied and applied in different ways to the orifice plate (front, back, 50% of surface, 100% of surface).			
	• For the clean orifice plates, it was noted that the discharge coefficient increased with Reynolds number, contrary to the guidance in ISO 5167:2003.			
	• For the contaminated orifice plates, it was found that the results were in line with previous work by TUV NEL. However, it was noted that there was a significant level of uncertainty associated with the associated change in discharge coefficient.			
	• For the grease contamination, it was noted that measurement error was very sensitive to the distribution of grease, particularly where this was close to the edge of the orifice.			
	• For 50% contamination, the shift in discharge coefficient was about 50% that for a fully covered plate.			
	• Tests performed at TUV-NEL have shown that the discharge coefficient shift can be negative or positive, depending on the height of contaminant. However, this is not replicated in CFD analysis, as the mechanism involved is not yet fully understood.			
	TUV-NEL identified a number of areas where further work could be considered to resolve ambiguities in some of the data. However, for the moment, National Grid believes it has sufficient information to implement the findings for the majority of cases.			
	For the second	project:		
	A report has be	en produced covering the re	sults of the investigation,	

nationalgrid The power of action.



	whereby the measurement bias on the seven offtake metering installations were predicted using CFD modelling. The highest bias predicted using CFD modelling was for the one installation that had sub-compliant length of upstream straight pipework (ref ISO 5167:2003), although the presence of a flow straightener could not be determined. However, measurement bias was also predicted for two of the six compliant installations. There were also indications that the magnitude of the bias was affected by which upstream filter was in use, where there was a choice.
	The report concluded that CFD modelling methods had been used to realistically assess the measurement error for the seven metering installations operating at typical conditions. The results were tested against a range of similar published data to confirm this. It was also concluded that the predicted measurement errors were not strongly related to Reynolds number, such that the results could be inferred for the full operating range of the metering systems.
	National Grid is now considering implementation of the CFD assessment method across all the other metering systems covering the gas flows into the other LDZs.
Collaborative partners	None
R&D provider	TUV NEL





16) Ensuring Safety on Gas Transmission Sites

Project title	Fire Protection for Fire Water Mains				
			Cas Transmission Above		
	Ignition Potential of PDA Devices on Gas Transmission Above Ground Installations				
Project Engineer	Michael Daniel, David C	Godwin			
Description of project	This area of our portfolio is made up of two projects.				
	used to mitigate corr	osion on buried stee event firewater mains	terial options that could be I firewater mains, and the being sited above-ground		
	staff using standard I		afety risks for operational dous areas, where there is r mixture.		
Expenditure for financial year	Internal £10kExpenditureinExternal £8kprevious(IFI)Total£18kfinancial years				
Total project costs (collaborative + external + internal) Technological area and/or	Projected 2009/10				
issue addressed by project	National Grid currently has below-ground steel fire water mains at AGIs, Compressor Stations, Reception Terminals and LNG facilities. However, a number of fire water mains have experienced leakage resulting from internal and external corrosion. There are also concerns about replacing the below-ground pipework on sites with contaminated land. Therefore, National Grid would like to consider the feasibility of above-ground fire water mains, such that inspection, maintenance and replacement could be undertaken with less expense.				
	The first project will therefore assess the additional risks that above- ground fire water mains will be exposed to. For example, flame impingement or thermal radiation in the event of a hydrocarbon pool or jet fire, blast damage due to a gas explosion, vehicle impact etc. The project will cover the risks associated with the following hazards:				
	Flammable and C	ombustible Liquids Sto	orage		
		ied Gases Storage			
	 High Pressure Na 	-			
	Storage of Flammable Materials in Containers, Drums and Cylinders				
	The second project will determine whether or not a standard (i.e. not IS certified) portable data apparatus (PDA) devices will be able to be used for routine maintenance work in potentially gas hazardous areas, in conjunction with appropriate and approved operating procedures.				
			PDA to determine under rk/ignition. NG will use the		





	device assessment report to develop a risk assessment and to decide any potential policy impact.				
Type(s) of innovation involved	Significant	Project Benefits Rating	Project Residual Risl	Overall Project Score	
		9 to 13	-2 to -3	12 to 15	
Expected benefits of project	For the first projec National Grid in id systems:				
	• The materials that could be used below-ground to mitigate the problems currently being experienced on steel firewater mains.				
		ve-ground firewate			
	Which materials ground firewater		for the constru	iction of above-	
	-	s should be taken	to:		
	 Prevent freezing of the fire water 				
	 Protect the main and its supports against flame impingement and thermal radiation. 				
	For the second project, the development of the design of a specific PDA device for use in potentially explosive atmospheres would be prohibitively expensive. Such a development would need to be led by the manufacturer and the development cost would be passed on to National Grid. As NG only expects to purchase around 200 PDA units for Gas Transmission, the cost per unit would be extremely high.				
	Rule of thumb is that data acquisition devices that have already been certified as intrinsically safe (IS) are typically around 4 times the purchase cost of standard devices. However, the specific PDA unit that is being used by NG for maintenance operatives is not currently available as an IS version.				
	If safe procedures can be developed to utilise the specific PDA device by Gas Transmission maintenance operatives, NG can than benefit from extending favourable terms already negotiated for Electricity Transmission.				
Expected timescale of project	2 years	Duration of once achieved		ears	
Probability of success	60%	Project NPV benefits – PV probability of s	costs) x £4k		
Potential for achieving expected benefits	Both these projects	were at early sta	ge at the end	of the year, with	





	nothing yet to suggest that the potential to achieve benefits had reduced.			
Project progress [Year to End of March 2009]	For the first project, the Major Accident Hazards that may put an above-ground firewater main at greater risk than a buried main have been reviewed. The Hazards considered have included external causes (aircraft damage), natural causes (earthquakes), external failure events (design/construction/inspection/testing, foundation failure, fatigue, corrosion), on-site causes (frost damage and ground heave, impact damage/missiles, explosion/overpressure effects, exposure to thermal radiation and flame impingement, human factors) and site-specific issues			
	For the second project, the test rig has been prepared for testing of the PDA units, the unit comprises of a 3m ³ explosion chamber fitted with a blow-off roof panel. In the rear of the chamber an idealised spark generator is fitted to which a PDA battery is attached. The chamber is purged filled remotely with a stoichiometric mix of gas and air and when stable conditions are achieved the idealised spark generator is started to conduct a test. The test arrangement is shown below.			
	<text></text>			
Collaborative partners	None			
R&D provider	GL Industrial Services (UK) Ltd			



17) Reducing Environmental Impact by Understanding/Reducing Methane Emissions

Project title	<i></i>			
	"M5" Emissions			
	 Improving the Integrity of Pig Trap Door Seals 			
	Alternatives to Venting from the NTS			
Project Engineer	Pete Smith , Matt Seco	mbe, Steve Johnstone &	lan Briggs	
Description of project	This programme of w	ork is made up of thre	e projects.	
			niques to quantify fugitive from compressor station	
	The second project is conducting research into the integrity management of the elastomer seal and seal housing, with respect to the reduction of fugitive methane emissions to the atmosphere from pig trap door seals.			
	The third project is to study and develop practical methods to reduce the emissions of methane that would otherwise occur during venting to the atmosphere from the natural gas transmission network.			
Expenditure for financial year	Internal £13k External £50k Total £63k	Expenditure in previous (IFI) financial years	£53k	
Total project costs (collaborative + external + internal)	£400k	Projected 2009/10 costs for National Grid	£260k	
Technological area and/or issue addressed by project	For the first project, fugitive leakage from National Grid's National Gas Transmission System (NTS) has been estimated to be of the order of 4000 tonnes per annum. Therefore, National Grid needs to be able to locate and quantify fugitive methane emissions so that the impact on the environment can be managed and mitigated. However, the existing safety-related gas detection systems (fixed point and hand-held gas-in-air concentration sensors) are not appropriate for this. Therefore, this project is evaluating a selection of techniques that could be brought together to conduct effective surveys with. The second project addresses the integrity of the large seals on pig trap doors. Although critical to the integrity of most hydrocarbon containment systems elastomer seals may easily be overlooked. They can fail through mechanisms such as extrusion damage, compression set, temperature and chemical degradation, swell/shrinkage and wear, or through rapid decompression damage. Elastomer failure may ultimately lead to loss of gas containment, although the leaks may be small enough not to be readily detected, but leading to significant fugitive emissions between inspections.			
	The second project therefore considers the principal types of closure employed on the National Transmission System and, for each of these, examines the typical modes of failure of the seal. Cross- industry failures are also considered. To mitigate the potential for seal failure, controls are investigated in an effort to define good practice in materials selection, maintenance & assurance practices.			



Fig 1 - Pig trap door with Ringlock closure at Paull AGI



The third project addresses the potential to reduce the amount of natural gas (typically 85-93% methane) that is vented to atmosphere by introducing new technologies and operating practices.

Planned venting can arise from a number of sources around the network, including venting at compressor sites and pipeline decommissioning prior to repairs, replacement or modification activity.

- Planned venting at compressor sites is monitored and recorded through the on-line control system. For 2007, NTS reported to the Environment Agencies that there had been 1887 tonnes of natural gas emitted by planned vented from compressor stations.
- Pipeline pressure is typically reduced to 7barg by recompressing it into an adjacent pipeline. However, the last 7barg can not be sensibly recompressed using the available equipment. It is therefore safely vented to atmosphere. Historical trends suggest that in excess of 150,000m³ of pipework volume is vented to atmosphere in this way each year (about 1000 tonnes of gas).

Clearly there are sound environmental and energy efficiency reasons for developing methods to reduce the amount of vented natural gas. There are several points that influence the current venting best practice, including both commercial and operational factors in addition to energy saving and environmental concerns. These concerns include the consideration of:

- Distance between pipeline block valves. These isolation distances are tending to increase and thus lead to increased vented volumes during decommissioning.
- Installation of Booster Units at Pig Trap or Block Valve Sites to enable better management of the decommissioning activities.

To improve the environmental performance of final stages of the decommissioning process several options are available including:



	Collect the gas and use elsewhere with the network.				
	• Flare the gas. Methane is recognised as having a significantly greater "Global Warming Potential" (GWP) than carbon dioxide, approximately twenty times. Thus flaring will reduce the environmental impact.				
	Use the gas at the	ne decommissionin	g site.		
Type(s) of innovation involved	Tech Transfer to	Project Benefits Rating	Project Residual Risk	Overall Project Score	
	Significant	15 to 17	-1 to -2	17 to 19	
Expected benefits of project	It hoped that the techniques being e benefits, including:-	valuated, which w			
	 More complete compressor sites 		of methane	emissions at	
	 Information to tailevels 	arget remedial ma	intenance to rec	luce emission	
	 Quantification of PPC reporting re 	f emissions with tl equirements	he aim of provic	ling input into	
	 Development of a historical track record upon which to build an on-going improvement plan. 				
	The expected benefits from the second project will be the transfer of knowledge from other related industry sectors to National Grid, enabling a plan to be produced to ensure good practice to be achieved in managing the integrity of elastomer seals in pig trap door closures				
	The expected bene	fits from undertakin	g the third projec	et are:	
		of new best pra g decommissioning			
		tional Grid's metha	ne emission inve	ntory	
	Improved energy				
	A financial benefit can be derived from consideration of reduced methane emissions. Natural gas emissions are recognised to be twenty times more damaging to the environment, such that methane might be expected to trade at around 25 times the £/tonne figure that CO2 is currently traded at, when methane is added to the European Emissions Trading Scheme.				
	Planned venting down of gas transmission pipelines for maintenance accounts for about 960 tonnes of methane emissions per year				
	tonnes (Advantio	for maintenance a ca Report 6446) of	accounts for mo methane emissio	re than 1800 ons per year	
		be captured and st ovide 5kWe / tonne		e used to fuel	



Expected timescale of project	4 years	Duration of benefit once achieved	5+ years			
Probability of success	60%	Project NPV = (PV benefits – PV costs) x probability of success	£1,000k			
Potential for achieving expected benefits	combination of techn fingerprint of methan increasing number of highlighting the impor	The first project is complete and has demonstrated that a combination of techniques can be used to develop a detailed fingerprint of methane emissions. For the second project, an increasing number of known failures on pig trap door seals is highlighting the importance of developing improvements, but the project is still in its early stages. The third project has only just started.				
Project progress [Year to End of March 2009]	completed at four com	pilot emissions surve pressor sites to demons results from the survey	trate the effectiveness			
	 "Emissions fingerprint" using mobile monitoring and GPS to identify main sources of emission. Portable meteorological data is also taken to use wind speed and direction to assist in pin-pointing sources of emission. 					
	• Site perimeter surveys to establish ground level emissions and quantify methane levels to determine if site emission affect by emissions from an external source. Also, this enables an "over-the-fence" estimate of emissions from the site impacting on the local environment.					
	 High-flow sampling results using proprietary equipment to quantify leakage from accessible site gas infrastructure. 					
	The data produced by the trial surveys enabled an estimate of the overall site methane leakage to be established. An example of the "emissions fingerprint" approach is shown in the cluster diagram below.					
	Fig 2 – Fugitive em	issions fingerprint of a c	ompressor station			
	pan 2					





Plans have been developed for the survey techniques to be implemented on surveys of all other compressor sites around the UK.

For the second project, an assessment has been completed and a report is in preparation. Data was collected through a variety of means including database and literature searches, interviews with personnel (both within National Grid and other operators and closure manufactures) and laboratory testing of components. Analysis of the data enabled trends to be determined and a definition for good practice to be formulated. A list of recommendations will be produced to enable the findings of the project to be readily implemented. Each recommendation is graded to allow prioritisation.

Fig 3 - Close-up of failed Ringlock seal (courtesy of GD Engineering)



The third project was fully scoped and sanctioned, ready to commence at the year end.

The picture below shows one of the large mobile recompression units which are already used to transfer gas between pipelines and thereby reduce the amount of gas vented to atmosphere prior to pipeline maintenance by 80-85%. It is anticipated that other new technologies will be identified as part of this project to improve this further.





	Fig 4 – Mobile re-compression unit		
	<caption></caption>		
Collaborative partners	None		
R&D provider	GL Industrial Services (UK) Ltd		





18) Reducing National Grid's Carbon Footprint

Project title	Reducing National Grid's Carbon Footprint				
Project Engineer	lan Welch				
Description of project	Knowledge and innovation search external to the existing energy providers, with a specific target being reducing energy losses, seeking alternatives to SF6 gas and reducing environmental impacts. This project is collaborative piece of work, which has both Gas and Electricity elements.				
Expenditure for financial year	Internal £4k External £12k Total £16k	Expenditure previous (financial years	in (IFI)	£20k	
Total project costs (collaborative + external + internal)	£36k	Projected 2009 costs for Nation Grid		£0	
Technological area and/or issue addressed by project	To search for and import technology propositions and solutions from non energy related R&D sectors (ie in this case the major UK provider for defence) which have potential for electricity (and gas) transmission				jor UK provider
Type(s) of innovation involved	Significant			Project sidual Risk	Overall Project Score
		10	0		10
Expected benefits of project	The expected benefits of this project are that it will help inform National Grid's strategy on how best to deal with a number of environmental issues and in doing so will potentially contribute financial savings in the form of Opex reductions and reductions in both financial and reputational risk to National Grid.				
Expected timescale of project	2 years	Duration of once achieved		efit 5 years	S
Probability of success	85 % Project NPV = (PV benefits – PV costs) x probability of success				
Potential for achieving expected benefits	Medium/High – Knowledge that solutions available to the defence sector are equivalent to / no better than those available to the energy sector would be treated as a successful outcome.				



Project progress [completion March 2009]	This two-year project is now complete. Work commenced with Qinetic to import knowledge into the energy sector of emerging research from the military sector. The project methodology was to undertake a sweep of emerging technologies and see how these might map across to electricity and gas transmission.						
	The initiating idea, a search for alternatives to SF6, proved not to be successful. However a number of other promising areas were assessed. The areas are:						
	 Unmanned aerial vehicles for surveillance of gas transmission assets and condition monitoring of overhead lines – with reduced carbon footprint and increased safety to personnel 						
	 Import of "stealth" technology to reduce the audible impact of transmission assets (e.g. reduced noise emissions) 						
	Specialised coatings e.g. lower thermal vulnerability to solar						
	Possible energy scavenging from waste heat sources						
	Where appropriate follow-on projects have been, or will be commenced						
Collaborative partners	National Grid Electricity Transmission						
R&D provider	Qinetiq						





19) Flooding Risk Analysis

Project title	Flooding Risł	Analysis	s Pluvial Flo	oding Risks		
Project Engineer	Doug Dodds	Doug Dodds				
Description of project	This is a joint project with National Grid Electricity Transmission to improve the understanding of pluvial flooding (also known as "flash flooding"), by relating potential fluvial, pluvial flooding and inundation maps to the National Grid Transmission assets on the National Grid GIS system, so that it can be used for planning and risk assessment purposes.					
Expenditure for financial year	Internal £4k External £4k Total £8k		Expenditur (IFI) financ	e in previous ial years	£0	
Total project costs (collaborative + external + internal)	£8k		Projected costs for N	2009/10 ational Grid	£0	
Technological area and/or issue addressed by project	The traditional assessment of flood risk is based on river levels (fluvial flooding) and coastal flooding. However, recent experience has shown the impact and potential impact of pluvial flooding, whereby local ground conditions and/or topography cannot handle severe rainfall over a sustained period of time. This project therefore aims to develop an improved understanding of how pluvial flooding (or "flash flooding") could affect National Grid Transmission assets. For Electricity Transmission, these include towers and substations; while, for Gas Transmission, these include metering offtakes, block valve sites, multijunctions and compressor stations.					
Type(s) of innovation involved	Significant		t Benefits ating	Project Resid Risk	lual	Overall Project Score
	olgimourit		6	0		6
Expected benefits of project	National Grid's Transmission licences require operation of networks with the minimum of disruption to service. Any preventable losses of service due to flooding should be mitigated through appraisal management and reduction of the flood risk. Climate change appears to be resulting in a greater frequency of flash flood events, similar to that experienced in June/July 2007.					
	Currently, National Grid undertake post flood surveys of all National Grid assets each time they potentially have been affected by a flooding event. It is envisaged that the solution being developed by this project will enable most assessments to be carried out remotely by cross-referencing details of at-risk components of the asset against the new data on pluvial flooding resulting from sustained heavy rainfall. This will result in significant OPEX savings in the aftermath of flash flooding events.					



Expected timescale of project	1 year	Duration of benefit once achieved	5+ years		
Probability of success	60%	Project NPV = (PV benefits – PV costs) x probability of success	-£24k		
Potential for achieving expected benefits	There is a high	likelihood of delivering the ex	pected benefits.		
Project progress [Year to End of March 2009]	Based on progress to the end of the year, delivery of the first round of LIDAR (Light Detection and Ranging) maps for the 1 in 100 risk sites is expected during summer 2009.				
		ongoing to assess National ironment Agency's surface w			
	Engagement on flood resilience has been initiated with CIRIA (Construction Industry Research & Information Association).				
Collaborative partners	National Grid Electricity Transmission				
R&D provider	Environment Agency, Network Mapping				





20) Asset Management and Performance of Energy Systems (Amperes)

Project title	Asset Management and Performance of Energy Systems						
Project Engineer	Jenny Cooper						
Description of project	The overall "Amperes" project is a collaboration between six universities and ten industrialists (including National Grid), addressing the following strategic key issues:						
	 The need to maintain reliable energy supply Ageing plant Changing requirements (environment) Renewable and distributed power generation Reduced skills base 						
	For this part of the project, GL are interacting with the universities on the gas transmission aspects, such as the modelling of the gas network and the interaction between gas and electric network models.						g of the gas
Expenditure for financial year	Internal £4kExpenditureinExternal £89kprevious(IFI)Total£93kfinancial years						
Total project costs (collaborative + external + internal)	£104k	С	Projected 2009 osts for Natic Arid		£11k	k	
Technological area and/or issue addressed by project	The convergence of vectors for energy generation, supply and use is causing increasing interplay between gas and electricity networks. This interaction is being modelled through close cooperation between GL and Edinburgh University					city networks.	
Type(s) of innovation involved	Significant	Pr	oject Benefits Rating		Proje sidual	ect I Risk	Overall Project Score
			7		0		7
Expected benefits of project	This overall project aims to improve the understanding of the impact on Gas and Electricity networks of current and future trends in energy supply and energy use. This will allow improved decisions to be made on the management of assets, and if a demand side approach to energy management can be adopted, it should allow CAPEX and OPEX to be reduced on energy transmission infrastructure.						
Expected timescale of project	4 years		Duration of once achieved		efit	5+ yea	rs
Probability of success	60%		Project NPV benefits – PV probability of s	costs	s) x	-£96k	





Potential for achieving expected benefits	The supply of gas network modelling software and provision or integration support from GL should help the overall project achieve its objectives.					
Project progress [Year to End of March 2009]	Methodologies to progress the project were formulated and agreed between GL and Edinburgh University. GL 'Synergee' network simulation software was licensed to Edinburgh University to allow them to construct network management models.					
	GL 'Synergee' software was used by Edinburgh University with additional modules to allow simulation of impact of changes in energy use and supply patterns. Integration with the additional modules was undertaken with support from the GL team.					
Collaborative partners	SUPERGEN V Amperes Consortium, specifically Edinburgh University.					
R&D provider	GL Industrial Services (UK) Ltd					





21) <u>PRCI</u>

Project title	PRCI					
	(Pipeline Research Council International)					
Project Engineer	Tony Stanabowar					
Description of project	Tony Stonehewer					
Description of project	contributions, based member company. projects that most	es a collaborative R&D p d on the total length of pipe Each member compar closely address their no cess to the output of the co	elines operated by each ny contributes to the eeds, but all member			
Expenditure for financial year	Internal £9k External £20k Total £29k	Expenditure in previous (IFI) financial years	£76k			
Total project costs (collaborative + external + internal)	\$9m	Projected 2009/10 costs for National Grid	£40k			
Technological area and/or issue addressed by project	The PRCI aims to conduct a collaboratively-funded research & development programme that enables energy pipeline companies around the world to provide safe, reliable, environmentally compatible, cost-efficient service to meet customer energy requirements.					
	programme launche included the following	research objectives) co ed in 2008 that were supp ng. Also shown for each a ribution and the supported	oorted by National Grid rea is the proportion of			
	 Time-dependent Corrosion and M 	Threat Management echanical Damage): 32%	(including External			
	acc	velopment of technologies urately identify and evalua pondment and shielding co	te the effects of coating			
		velop technologies to loo rosion in difficult to inspect				
	 Develop and validate tools and inspection-based procedures for the accurate and reliable location, sizing and characterization of mechanical damage defects. 					
		nt Threat Management er and External Force): 479				
	inte sys	nceptual demonstration of grity and security mar tem and the development its implementation.	nagement surveillance			
		velopment of quantitative ed methods for assess				

nationalgrid The power of action.



		rema	aining life of gouges and dents + gouges.			
			duct field testing and demonstrate the bilities of the intrusion sensor system.			
		asses sever with/v impro	elopment of improved, qualitative and validated essment tool for ranking and screening the prity and remaining life of plain dents, without associated corrosion or welds to ove industry's response to concerns about the inuing occurrences of damage to pipelines.			
			stigation to better define the effectiveness of fabric applications for reducing soil loads.			
	Design ar	d Constr	truction: 9%			
			elopment of next generation tensile strain limit els to support strain-based design procedures.			
		elop a risk based design and standards to sure and improve the safety of natural gas and d pipelines and gain the broad acceptance lators and industry.				
	 Reduce the uncertainty of Automate Technique (AUT) detection and sizing of dramatically improving the predicted pipeline. 					
	Compres	or & Pur	mp Stations: 7%			
			uce the total costs of ownership & operation of turbines.			
			racterize compressor station greenhouse gas sions and identify mitigation opportunities.			
		inves comp losse	racterize Facility Integrity status and issues, and stigate Balance of Plant (non-driver, non- pressor) to identify opportunities to reduce es, increase reliability, and reduce O&M costs of systems & components.			
	Measurer	ient: 5%	, o			
		impro	uce lost and unaccounted for gas expense via oved accuracy, reduced bias and increased ating range of conventional measurement ons.			
			te a comprehensive summary of all available arch related to gas flow measurement			
Type(a) of innovation involved	Incremental		ct Benefits Project Residual Overall Rating Risk Project Score			
Type(s) of innovation involved	To Significant		11 -2 13			



Expected benefits of project	PRCI's value proposition: "Formal cost / benefit studies of member participation show a consistently positive ratio of 4:1 to 7:1 from reduced costs of operations and maintenance, inspection, materials, design, construction and testing" National Grid Transmission and National Grid Gas Distribution this year used their combined annual contribution of \$131k to help launch 24 PRCI projects with a total cost of \$2.68m. This provides an					
	average leverage on projects of over 20:1.					
Expected timescale of project	5 years	Duration of benefit once achieved	5+ years			
Probability of success	35%	Project NPV = (PV benefits – PV costs) x probability of success	£124k			
Potential for achieving expected benefits	The PRCI collaborative programme gives National Grid opportunity to benefit from a significant number of highly leverag projects which compliment much of the work on the overall programme.					
Project progress [Year to End of March 2009]	The following N year by PRCI:	National Grid supported proj	ects were launched this			
	Time-Deper	ndent Threat Management				
		ge-Scale Cathodic Disbondm	ent Testing for Coal Tar			
		amel (CTE) iable Cathodic Protection Cri	toria			
		ermine In-Line Inspection To				
		aracteristics				
		eline Facility Incident Data Re alysis	eview and Statistical			
		eline Facility Threat Identifica sceptibility Methodology	tion and Failure			
	o Ab o	ove Ground Surveys For Diffi	cult to Assess Areas			
		nanced Mechanical Damage chanical Damage Assessmer				
	∘ Ultr	asonic Measurements of Stra	ains in Pipelines			
		endent Threat Management	•			
		nceptual Pipeline Integrity & S				
		oustic Source Level and Signation eline Scratches and Gouges	ature Measurement of			
		d Tests and Advanced Deve nsor System	lopment of Pipeline			
		-scale Experimental Validation mage Assessment Models	on of Mechanical			
	∘ Ful l	-scale Experimental Validation mage Assessment Models (Ir				
	 Model for Predicting the Likelihood and Severity of Newly 					
		200	tional grid			





		Created Damage		
	0	Full-Scale Buried Pipe Tests to Determine and Reduce Soil Loads on Buried Pipelines		
	 Design 	& Construction		
	0	Tensile Strain Limits for Strain Based Design		
	0	Standardization of Natural Gas Reliability Based Design and Assessment Methodology		
	0	Advanced Technologies and Methodology for Automated Ultrasonic Technique (AUT) Systems Qualification		
	Compressor & Pump Station			
	0	Gas Turbine Component Research Prioritization		
	0	Methods to Reduce the Carbon Footprint of Pipeline Stations		
	0	Compressor & Pump Station Facility Integrity		
	 Measu 	rement		
	0	Flow Measurement with Low Differential Pressure		
	0	Assessment of Dirty Meter Performance		
	0	Measurement Research Compendium		
		vere delivered by PRCI during the year for the following arid supported projects:		
	 Project 	s Launched in 2007/08		
	0	Understanding Magnetic Flux Leakage (MFL) Signals from Mechanical Damage in Pipelines		
	0	Development of a pipeline encroachment prediction model		
	0	Evaluate Existing Hydrocarbon Dewpoint Measurement Equipment		
	0	Clamp-on Ultrasonic Meter to Confirm Conditioned Flow at Primary Meter		
	0	Meter Station Measurement Uncertainty Analysis Tool		
	 Project 	s Launched in 2008/09		
	0	Pipeline Facility Incident Data Review and Statistical Analysis		
Collaborative partners	energy pip	arid Gas Distribution (UK) and 38 other companies with beline interests (27 based in the USA 5 European; 4 1 South American; 1 Middle-Eastern)		
R&D provider	multi-discip	s a selection of Research Contractors, including large, bline corporations, non-profit institutions, small, pipeline , major colleges and universities.		



22) Carbon Capture and Stor	rage (Strategic Ove	<u>rview)</u>				
Project title	Carbon Capture and Storage					
Project Engineer	Dominic Harrison					
Description of project	High level technology review of carbon capture and storage, including the impact it will have on energy markets, the key issues facing its deployment in Europe and developments around the world where appropriate, and potential impact on gas and electricity networks					
	and implication		or coal and gas-fired plant blogies for CO2 network etc			
	Carbon Storage and future devel		age projects (e.g. Snøhvit)			
Expenditure for financial year	Internal £4k External £41k Total £45k	Expenditure in previous (IFI) financial years	£0			
Total project costs (collaborative + external + internal)	£45k	Projected 2009/10 costs for National Grid	£0			
Technological area and/or issue addressed by project	The project will pro	duce a report addressing	g the following issues:			
	Short Term					
	Transportation – Ju Grid already has pr		bleteness, because National			
	Policy Environmer proposals and deve		sing in on the recent EU			
			2 vs. Supercritical (Dense existing gas transmission			
	on development of		ameworks that will impinge regard to the CO2 pipeline			
	frameworks, includi	ing how a Cos transport ect of HSE and adoptin	outlook for Regulatory system might be regulated, g methodologies already in			
	Longer Term					
		 Developments at EU accelerators and brakes 	and National level and the			
	Technical Standards – Review of European and UK approaches and the development paths of likely frameworks.					
		y evolution at EU and evelopments in the UK.	Member States levels with			
	Legislation – Longe	er term evaluation.				
		Characteristics – Hand rements and implications	ling of transient conditions, 5.			





	CCS Deployment in UK – State of play in UK, CCS competition and longer term outlook for attractive sites.				CS competition and
Turne (a)	Dedical	-	ct Benefits Rating	Project Residual Risk	Overall Project Score
Type(s) of innovation involved	Radical		11	3	8
Expected benefits of project	can have on th	e Natior	nal Grid busi	iness is critical if	impacts that these consideration is to ansportation assets
Expected timescale of project	1 year		achieved	of benefit once	5+ years
Probability of success	60%		Project NPV = (PV benefits – PV costs) x probability of success		-£39
Potential for achieving expected benefits	The work has been completed, the output being a comprehensive high level review, which gave National Grid the confidence to commission a more detailed project to assess the re-use of a gas transmission pipeline for CO2 transportation (see next project).				
Project progress [Year to End of March 2009]	National Grid commissioned Pöyry Energy Consultants in May 2008 to undertake an assessment and provide a detailed report of the scale and impact of a potential CCS (Carbon, Capture & Storage) market developing in the UK. This report would further National Grid's understanding of CCS, and in particular provide an indication of the potential for re-use of its NTS assets by considering the potential CO2 volumes involved, and the location of possible CCS markets.				report of the scale & Storage) market er National Grid's an indication of the g the potential CO2
	The report provided by Pöyry examined the key issues facing the deployment of CCS, focusing on Europe, but also assessing the developments around the World where relevant. The report examined the key developments of coal and gas-fired plant and considered the different technologies being considered for different plant types. The implications that these had on transportation of CO2, such as level of contaminants and operating pressures, were also considered. The report also included an assessment of the most likely locations in the UK where CCS could be deployed, again providing an insight into the extent of any role National Grid could offer in the roll-out of CCS.				also assessing the ne report examined and considered the nt plant types. The 02, such as level of o considered. The ely locations in the an insight into the
	The report modelivered within			of the Project S	Sanction and was
Collaborative partners	None				
R&D provider	Pöyry Energy				



23) Re-Use of Transmission Assets for the Transportation of CO2

Project title	Reuse of Trar	Reuse of Transmission assets for the Transportation of CO ₂					
Project Engineer	Julian Barnet	Julian Barnett					
Description of project	Develop knowledge on how the existing National Transmission System (NTS) pipeline network could be utilised to transport anthropogenic CO_2 and how current assets will perform when transporting gas with different physical properties. The work will also consider the potential health and safety implications from transporting CO_2 in the existing NTS network.						
Expenditure for financial year	Internal £4k External £92k Total £96k		Expenditur previous financial ye	(IFI)			
Total project costs (collaborative + external + internal)	£475k		Projected costs for Grid	2009/10		ĸ	
Technological area and/or issue addressed by project	The issue being addressed by this project is to determine the abilit of National Grid's existing NTS assets to transport anthropogeni CO _{2.}						
	Rating Risk Project					Overall Project Score	
Type(s) of innovation involved	Radical -		12	2		10	
Expected benefits of project	in reducing t whole by prov helps to imp	he CO ₂ viding the prove se e of fos	emissions e ability to tr curity of su sil fuels (su	of the UK' ansport CO upply for th	s energ 2. The p ne UK	hal Grid to assist y industry as a project potentially by allowing the ower generation,	
	The project will also allow National Grid to gain knowledge on how to utilise existing assets to allow the transport of CO ₂ through the existing pipeline network. It is hoped that the work will demonstrate that it is economic and efficient to re-use National Grid assets to help meet the environmental and energy challenges of the future as well as providing improved "green" credentials for the business.					CO ₂ through the will demonstrate id assets to help the future as well	
Expected timescale of project	2 years	Duration of benefit once 10+ years achieved					
Probability of success	60%	Project NPV = (PV benefits – PV costs) x £5,000k probability of success					



Potential for achieving expected benefits	The project needs to explore a large number of technical issues and many of these still need a lot of work before the potential can be meaningfully assessed.
Project progress [Year to End of March 2009]	The services of Pipeline Integrity Engineers (PIE) Limited were engaged in the autumn of 2008 to assist National Grid develop its understanding of Carbon Dioxide (CO_2) and the application of its pipeline knowledge to potential Carbon Capture and Storage (CCS) projects.
	During the period up to end of the 2008/09 financial year the following preliminary analysis work was undertaken by PIE:
	 CO₂ gas dispersion and the likely hazard distances.
	 Derivation of individual risk transects for two gas CO₂ pipeline release scenarios.
	 Development of a possible specification for anthropogenic CO₂.
	 Obtaining information regarding knowledge and experience on CO₂ pipeline systems in America.
	Application of current pipeline codes.
	 Initial assessment of material and integrity issues.
	PIE have also been working closely with National Grid to develop a detailed Research and Development (R&D) programme to underpin and develop knowledge relating to CO ₂ and CCS transportation infrastructure.
	The intention is to also engage the services of Penspen Limited to:
	 Conduct front end engineering work into the possible use of existing National Grid pipeline assets and the development of independent pipeline networks for the transportation of CO₂.
	 Develop an understanding of and acceptable approach to managing fracture mechanics issues associated with CO₂ pipelines in the UK.
	Engagement of Penspen has been delayed while the range of the work required from them has been more fully developed based on the preliminary analysis undertaken by PIE and agreement is reached between National Grid and Penspen regarding the Terms and Conditions (T&Cs) for the contract proposed. The intention is for Penspen to commence work shortly.
Collaborative partners	None
R&D provider	Pipeline Integrity Engineers (PIE) Penspen